

जिला खनन कार्यालय, वैशाली

पत्रांक..... / एम0, दिनांक.....

सेवा में,

M/s Aayushman Enterprises

Prop- Mr. Shrikant Kumar

S/o Ramdas Ray

At- Garha, Block-Bochaha ,

Muzaffarpur, Bihar-843103

विषय:- खनन योजना (Mining Plan) अनुमोदन के संबंध में।

महाशय,

उपर्युक्त विषय के आलोक में कहना है कि वैशाली जिलान्तर्गत हाजीपुर अंचल के मौजा- पहेतिया, थाना संख्या-60 खाता संख्या-372, 139, 63 एवं 358 खेसरा संख्या-280, 281, 283, 282, 284 एवं 287 रकबा 3.38 हेक्टेयर में लघु खनिज साधारण मिट्टी के खनन हेतु प्रस्तुत खनन योजना का अनुमोदन संयुक्त सचिव, खान एवं भूतत्व विभाग, बिहार, पटना के पत्रांक- 4156/एम0, दिनांक 27.12.2016 के आलोक में निम्न शर्तों के साथ अनुमोदन किया जा रहा है।

1. खनन योजना का अनुमोदन 56,277 घन मी0 एक वर्ष तक साधारण मिट्टी के उत्पादन हेतु अनुमान्य किया गया है।
2. खनन कार्य से पूर्व संबंधित जिला खनन कार्यालय में रॉयल्टी जमा कर खनन की अनुमति लेना अनिवार्य है।
3. खनन कार्य हेतु सम्बंधित विभागों/संस्थाओं से अनापत्ति पत्र आवश्यक होगा।
4. साधारण मिट्टी खनन की गहराई सतह से 02 मीटर से अधिक नहीं होगा।
5. खनन कार्य ग्राउण्ड वाटर लेवल से कम से कम 02 मीटर उपर तक ही सीमित रखा जाएगा।
6. प्रस्तावित उत्खनन की गहराई के कम से कम आधे के बराबर चौड़ाई रखने वाले सटे मैदानों की सीमा से पटरी छोड़ दी जाएगी।
7. ईट निर्माण, पथ निर्माण, तटबंध निर्माण आदि के प्रायोजनार्थ ईट मिट्टी और साधारण मिट्टी के खनन/ उत्खनन से संबंधित क्रिया-कलाप में विस्फोटक का प्रयोग नहीं होगा।
8. खनन/ उत्खनन संबंधी क्रिया-कलाप कार्य क्षेत्र के सामान्य जल निकासी के प्रतिरूप (पैटर्न) को परिवर्तित नहीं करेगा।
9. खोदे गए/ उत्खनित गड्ढा (पिट) को परियोजना प्रस्तावक द्वारा उपयोगी प्रयोजन (प्रयोजनों) के लिए पुनः स्थापित किया जाएगा।
10. खोदे गए/ उत्खनित गड्ढा के चारों ओर समुचित घेराबंदी कर दी जाएगी, ताकि किसी दुर्घटना से बचा जा सके।

11. ढुलाई के दौरान खोदी गई/ उत्खनित मिट्टी के फैलने से धूल उत्सर्जन को रोकने के लिए उपाय किए जाएंगे।
12. मिट्टी के खनन/ उत्खनन के कारण सृजित जल निकायों में रोग वाहकों (बैक्टर) के प्रजनन के कारण स्वास्थ्य खतरों के विरुद्ध सुरक्षा मानक अपनाये जाएंगे।
13. कामगारों/ मजदूरों को पेयजल और सफाई संबंधी सुविधाएँ प्रदान की जाएँगी।
14. किसी उत्खनन क्षेत्र की परिधि से किसी आर्सेनिक संरचना की दूरी कम से कम 15 मीटर रखी जाएगी।
15. राष्ट्रीय पार्कों और वन्य प्राणी अभ्यारण्य की सीमा के 1 किलोमीटर के अन्दर उत्खनन के क्षेत्र के मामले में ईट मिट्टी अथवा साधारण मिट्टी के खनन/ उत्खनन की अनुमति नहीं दी जाएगी।
16. खनन योजना में खनन कार्य बेंच बना कर किया जाएगा जिसकी अधिकतम उँचाई 2 मी० एवं चौड़ाई कम से कम 3.0 मीटर होनी चाहिए।
17. खनन कार्य के दौरान निकाले गये टॉप स्वायल को व्यवस्थित रूप से एकत्रित कर रखा जाएगा, जिसे खनन कार्य समाप्त होने के उपरान्त उसी क्षेत्र में फैला दिया जाएगा।
18. खनन योजना में वर्णित भूमि के स्वामित्व तथा भूस्वामियों की सहमती से संबंधित अभिलेखों की पूर्ष्टि करा लिया जाना अपेक्षित होगा।
19. भविष्य में किसी प्रकार की कोई भी गलती खनन योजना अथवा कार्य में पायी जाएगी तो खनन योजना स्वतः निरस्त माना जाएगा।


हो/-

खनिज विकास पदाधिकारी,
जिला खनन कार्यालय,
वैशाली।

ज्ञापांक 1322...../एम०, दिनांक 18/12/24.....

प्रतिलिपि:- निदेशक, खान एवं भूतत्व विभाग, बिहार पटना को सूचनार्थ प्रेषित।

प्रतिलिपि:- M/S PRANEJA ENVIROCARE & MANAGEMENT PVT. LTD., ASHIYANA, KHAJPURA, PATNA-800014 को सूचनार्थ प्रेषित।



खनिज विकास पदाधिकारी,
जिला खनन कार्यालय,
वैशाली।

Mining Plan & Mine Closure Plan

Minor Mineral- Ordinary Earth

Submitted under rule (17) of Bihar Minerals (Concession, Prevention of Illegal Transportation & Storage) Rules, 2019 amended till date

(Category-B2 as per EIA notification 2006 amended till date)

MAUZA-PAHETIYA, BLOCK- HAJIPUR,
DISTRICT- VAISHALI (BIHAR)

Total Lease Area: 3.38 Ha. (8.35 acres)

Plan Period: 1 Year


APPROVED

Mineral Development Officer
Vaishali

Letter No. 1322, Date 13/12/24

Applicant

M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, Block-Bochaha,
Muzaffarpur, Bihar-843103

Prepared by

M/s Praneja Envirocare & Management Pvt. Ltd.
Ground, Opp. Vamika Apartment,
Near Passport Office, Ashiyana,
Khajpura, Patna-800014 (Bihar)
Ph. 0612-2581824, 9708251824
email: - pemanagementindia@gmail.com
RQP: Sl. No.-30/ M.No. - 3825 DT. 07.11.2019

CERTIFICATE

I **Shrikant Kumar** S/o Ramdas Ray resident at- Garha, P.S.- Bochaha, Muzaffarpur, Bihar-843103, the lease/land holder of Soil Mining project for Soil (Mineral) over **3.38 Hectares**, in **Pahetiya mauza in Hajipur block of Vaishali district** hereby solemnly affirm that the plans and programs in this Mining Plan will be scrupulously implemented by me/us and I/We will be strictly held responsible for any deviation thereof. I/We also hereby certify that the provisions of Mines and Minerals (Development and Regulation) Act 1957, and along with the provisions of Bihar Mineral (Concession, Prevention of Illegal Mining, Transportation and Storage) Rules, 2019 and subsequent amendment will be strictly adhered to while implementing this Mining Plan and wherever specific permissions will be required. I/We will approach the concerned authorities of Director, Mines & Geology, Government of Bihar as the case may be.

Date:

Place:



Shrikant Kumar
(Authorized Signatory)
Aayushman Enterprises

AUTHORISATION LETTER BY THE APPLICANT

I, **Shrikant Kumar** S/o Ramdas Ray resident at- Garha, P.S.- Bochaha, Muzaffarpur, Bihar-843103 hereby do authorize M/s. Praneja Envirocare & Management Pvt. Ltd, RQP to prepare the Mining Plan submitted under the notification of Ministry of Environment, Forest and Climate Change & Rule No 17 of Bihar Minerals (Concession, Prevention of Illegal Mining, Transportation & storage) Rules 2019 amended till date in respect of **Thana No.-60 Khata No.- 372, 139, 63 & 358 Khasra No.- 280, 281, 283, 282, 284 & 287 at Mauza- Pahetiya, Block- Hajipur, District- Vaishali, Bihar**

I request The Directorate, Mines and Geology, Bihar government to make further correspondence regarding Mining Plan to answer your query and clarification to the RQP. He/She is also authorized to collect approved mining plan.

Name of RQP: **M/s. Praneja Envirocare & Management Pvt. Ltd, Memo No. – (Sl. No.- 30/ M. No.- 3825 DT. 07.11.2019 of Dept. of Mines & Geology, Govt. of Bihar).**


Praveen Kumar Roy (Mining Engineer)

Mob: 9708251824,

Address: Ground Floor, Opp. Vamika Apartment,
Near Passport Office, Ashiyana,
Khajpura, Patna-800014 (Bihar)
Email ID : pemanagementindia@gmail.com

Date:

Place:



Shrikant Kumar
(Authorized Signatory)
Aayushman Enterprises

CONTENT

SL.NO.	PARTICULARS
1.	Introduction
2.	Project Description
3.	Location, General and Accessibility
4.	Geology & Exploration Topography
5.	Mines & Mining Method
6.	Drilling and blasting
7.	Mine Drainage System
8.	Stacking of Mineral Rejects and Waste Disposal Arrangements
9.	Anticipated Environmental Impacts, Mitigation Measures and Environmental Management Plan
10.	Mine Closure Plan

LIST OF ANNEXURES

SL. NO.	TITLES
1	Consent & Declaration
2	Notifications & Copy of RQP Certificate
3	I.D. of Applicant
4	Copy Of Land Agreement / Deed/ Revenue Receipt
5	Location Map/Cadastral Map/ Khasra Map
6	Copy of Work Order/ Sanction/Lol
7	Map & Plates

श्रीमती सुनील



CHAPTER-I

1. INTRODUCTION

1.1	Applicant Name & Full address Contact No. & E-mail ID	M/s Aayushman Enterprises Prop- Mr. Shrikant Kumar S/o Ramdas Ray At- Garha, Block-Bochaha , Muzaffarpur, Bihar-843103 Mob: +91-9135603592 Email ID:			
1.2	Applicant's post/social status	Individual/Proprietorship			
1.3	Mineral or Minerals which the applicant intends to mine	Earth/ Soil			
1.4	Applied area for mining lease	Mauza- Pahetiya, Block- Hajipur, District- Vaishali (Bihar)			
		Thana No.	Khata No.	Khesra No.	Area (acres)
		60	372, 139, 63 & 358	280, 281, 283, 282, 284 & 287	3.38
		Total			3.38
1.5	Mineral (s) which are occurring in the area and which the applicant intend to mine	Ordinary Earth			
1.6	Period for which mining lease granted/ renewed/ proposed to be applied	Validity: 1 Year			
1.7.1	Name of RQP preparing the mining plan	M/s. Praneja Envirocare & Management Pvt. Ltd, Memo No. – (Sl. No.- 30/ M. No.- 3825 DT. 07.11.2019 of Dept. of Mines & Geology, Govt. of Bihar). Praveen Kumar Roy (Mining Engineer) Mob: 9708251824			
1.7.2	Address	Ground Floor, Opp. Vamika Apartment, Near Passport Office, Ashiyana, Khajpura, Patna-800014 (Bihar)			
1.17.3	Mobile Number & E-mail ID	Mob: 9708251824 Email ID: pemanagementindia@gmail.com			
1.8	Name of the prospecting agency	The base data and information is collected from various geological report of the department of Mines & Geology and local authorities as well as detailed prospecting of the area is carried out by the RQP			
1.9	Reference No. and date of the grant / communication received from the state Govt.	RQP certificate copy as Annexed			

श्रीमंत ठाकुर



CHAPTER-2

2. PROJECT DESCRIPTION

2.1. JUSTIFICATION OF PROJECT

The proposed project is a mining of earth/ Soil at *Mauza- Pahetiya Block- Hajipur, District- Vaishali (Bihar)*. The proposed project is having lease area of 3.38 Ha falls under Category- "B2" as per EIA Notification 14th September 2006 and subsequent amended, of the Ministry of Environment Forests & Climate Change, New Delhi.

The proposed production capacity of soil/ earth is **56,277 cum (86,104 tones) for 1 year**. The proposed area is Rayati property. **(Land documents enclosed)**.

Earth shall be excavated and used for commercial purpose (Land filling work), thus as per notifications, prior environment clearance is required. **(work order enclosed)**

It is for this purpose that 'Mining Plan' is being drawn so that all its aspects are taken care of justifiably, according to law, protecting the environment, removing all adverse impacts and creating a direct and indirect employment opportunities, improving socio- economic conditions of the local inhabitants and all-around status of life, achieving thereby a sustainable development.

2.2 BACKGROUND OF THE PROJECT

The Department of Mines & Geology, Bihar required under Bihar Minor Mineral (Concession, Prevention of illegal mining, transportation and storage) Rules, 2019. The general conditions of mining lease for minor minerals are mentioned here below:

- ✓ Under rule 17(4) Approval and submission of mining plan- All mineral concession holder or the government/corporation as the case may be shall submit a mining plan duly prepared by an RQP and approved by the Director or any officer/ person/ academic institution/govt. agency authorized by the dept. in this regard within a period of three months from the date on which communication regarding grant of mineral concession is received or such other period as may be decided/ allowed by the dept. for the submission of the approved Mining Plan.
- ✓ While preparing the Mining Plan, proper attention has been paid to ensure that the relevant provisions under MMDR Act-1957, MMR-1961, and Mines Act-1952 & Mines Rule- 1955 have been followed. All safety measures, provided in the statute, will be taken into consideration. On 17-09-2019 Bihar govt. took its policy decisions vide notification no -4/v.Mu-20-93/ 18-3174/M. That all Mining Lease/Settle under rule 17 of the said rules, the Lessee shall submit a Mining Plan with Progressive Mine Closure Plan for approval to the competent officer, Department of Mines & Geology, Bihar.
- ✓ Mining operation to be in accordance with Environmental Clearance.
- ✓ For baseline data assistance has been taken from the data, available from local authority.

2.3 RESTRICTED AREAS FOR EARTH QUARRYING

- I. The activity associated with mining / excavation of brick earth and ordinary Soil / earth for purpose of brick manufacturing, construction of roads, embankments etc. shall not involve blasting.
- II. The mining / excavation activity shall be restricted to a maximum depth of 2m below normal ground level at the site.
- III. The mining / excavation activity shall be kept above the ground water table at the site.
- IV. The mining / excavation activity should not alter the natural drainage pattern of the area.
- V. The mined/ excavated pit shall be restored by the project proponent for useful purpose(s).
- VI. Appropriate fencing all around the mined / excavated pit shall be made to prevent any mishap.
- VII. Measures shall be taken to prevent dust emission by covering of mined /excavated earth during transportation.
- VIII. Safeguard shall be adopted against health risks on account of breeding of vectors in the water bodies created due to mining/ excavation of earth.
- IX. Workers / laborers shall be provided with facilities for drinking water and sanitation.

Signature



- X. A berm shall be left from the boundary of adjoining field having a width equal to at least half the depth of proposed excavation.
- XI. A minimum distance of 15 m from any civil structure shall be kept from the periphery of any excavation area.
- XII. No mining of earth / excavation of brick earth or ordinary earth shall be permitted in case the area of mining excavation is within 1km of boundary of national parks and wild life sanctuaries:

श्रीमति कृष्णा



CHAPTER-3

3. LOCATION, GENERAL AND ACCESSIBILITY

3.1 LOCATION

(a) Details of the area

(i)	Lease-hold area				
	Location	Mauza- Pahetiya, Block- Hajipur, District- Vaishali (Bihar)			
		Thana No.	Khata No.	Khesra No.	Area (acres)
		60	372, 139, 63 & 358	280, 281, 283, 282, 284 & 287	3.38
		Geo-Coordinates of the project sites			
		Block-A	A	25°45'42.81"N	85°13'33.55"E
			B	25°45'42.13"N	85°13'37.13"E
			C	25°45'41.47"N	85°13'36.97"E
			D	25°45'40.25"N	85°13'44.04"E
			E	25°45'43.16"N	85°13'44.82"E
			F	25°45'43.82"N	85°13'41.21"E
			G	25°45'45.58"N	85°13'41.42"E
			H	25°45'45.81"N	85°13'36.95"E
			I	25°45'46.27"N	85°13'34.61"E
		3.38 Ha.			
(ii)	Mining Lease Map	Mining lease Google Map is attached			
(iii)	District & State	Vaishali district of Bihar			

(b) Key plan of area: -

Key plan of the site.

Total mining area is completely outside of any restricted or protected area by any state or central government.

3.2 GENERAL

(a) Mineral being worked	Soil/Earth
(b) Period of Mining Lease	1 Year from the date of execution
(c) Category of Land used	Raiyati Land
(d) Range of Block Proposed area	Area 3.38 Ha
(e) Existing pits	There is no pit available in the proposed Applied Area.

3.3 ACCESSIBILITY

Vaishali is one of the 38 districts of Bihar. The name derives its name from King Vishal. Even before the advent of Buddhism and Jainism, Vaishali was the capital of the vibrant Vajji confederation, since before the birth of Mahavira (c. 599 BC), which suggests that it was perhaps the first republic in the world, like those later found in ancient Greece. In that period, Vaishali was an ancient metropolis and the capital city of the republic of the Vajji confederation of Mithila, which covered most of the Himalayan Gangetic region of present-day Bihar.

TRANSPORT FACILITIES

Hajipur is the head quarter of Vaishali district and it is the main market for sand business. Due to high demand, often sand from Ganga, Gandak and other rivers are transported to Patna and other districts to fulfil the demand.


Nearest major roads are SH-74 and SH-93 are situated in the eastern direction of Gandak River and northern direction of Ganga River respectively. NH-19, NH-103 and NH-77 are situated in the northern direction of

Signature



Ganga River. Hajipur junction railway station is the major railway station and Jay Prakash Narayan International Airport is the nearest airport to the Vaishali district.

LOCATION MAP OF THE MINE AREA



सीमांत कुमल



CHAPTER-4

4. GEOLOGY & EXPLORATION TOPOGRAPHY

4.1 GEOLOGY

LOCAL GEOLOGY

The area comprises thick quaternary sediments ranging in age from Pleistocene to recent and are classified into three stratigraphic units such as (i) Sonpur/Hajipur formation, (ii) Vaishali formation and (iii) Diara formation. Sonpur/Hajipur formation comprises clayey sediments of the oxidized older alluvium of Pleistocene to early Holocene age. Vaishali formation represents the unoxidized silty deposits of middle to late Holocene age. Diara formation constitutes sand, silt and clay deposits of recent times confined within the firm banks of the rivers as well as sandy deposits in channel and point bars.

Lithology	Geological Unit	Age	Nature
Loose sand, silt, loam and their admixtures/fine to coarse sand	Diara formation	Late Holocene	Flat or gentle slope; soft unconsolidated Quaternary sediments mostly inundated in rainy season, bank erosion and redeposition
Unoxidised clayey silt or sandy silt	Vaishali formation	Middle to Late Holocene	Gentle slope; unconsolidated sediments prone to flooding in rainy season
Oxidised brownish yellow silty clay impregnated with caliche	Sonpur/Hajipur formation	Pleistocene to Early Holocene	Consolidated compact Quaternary sediments

REGIONAL GEOLOGY

Regionally, the area constitutes a part of the Ganga River Basin. The north-eastern part is predominantly characterized by sedimentary lithology in the Sub-Himalayan zone comprising Subathus, Dagshais, Kasaulis and Siwaliks. A general Regional stratigraphic sequence of the area is given below.

Geologically, it represents nearly two third of Bihar is under cover of Ganga basin composed of alluvium and masks the nature of basement rocks.

Geological succession and their Geographic distribution

Age	Geology	Geography
Quaternary	Alluvial deposits (Sand/ Clay, Silt, fragments)	North Bihar plain & Centre Bihar Plan
Tertiary	Sand, Stones and Clay stones	North Champaran Hills
Gondwana	Coal Measures forming a series of small outlier basins	Banka district
Vindhya	Sand, stones shales, Limestone etc.	Geography part of Bhabhua and Rohtas district
Satpura	Schist, Phyllite, Quartzite	Part of Aurangabad, gaya, Nawada, Nalanda, Sheikhpura and Munger districts of Bihar
Proterozoic	Mica Schist, amphi-Bolitr, quartzite, Granite, dolerite and pegmatite	Nawada Jamui & Banka
Achaean	Gneisses, Granite, Schist, phyllite, amphibolite, quartzite and intrusive all metamorphosed Sedimentary and Igneous rocks	Parts of Aurangabad, Gaya, Nawada, Jamui, Banka and Bhagalpur

Handwritten signature



Nearly two third of Bihar is under cover of Ganga herein compared of alluvium and marks the nature of basement rocks.

4.2 PHYSIOGRAPHY

- **General Landforms:** The district constitutes a flat-landscapes sloping gently towards southeast and belongs to the Ganga River basin; the western fringe being a part of Gandak sub-basin and the whole eastern part under the Burhi Gandak subbasin. The highest elevation is 51 m and the lowest 46 m amsl. The area may be classified into two major geomorphic units: recent flood plain and older flood plain with palaeo levee complexes, the former represented by diara Formation and later by Vaishali Formation and Sonpur/ Hajipur Formation.
- **Soil and rock pattern:** Vaishali district is characterized by a wide variety of soils which can be broadly grouped into two categories according to U.S Survey Staff in 1975.
 - 1) Entisols: They are younger alluvial soils locally known as Balsundari. They are deficient in nitrogen, phosphoric acid but generally rich in potash and lime. The Balsundari soils are generally a light friable loam with higher portion of sand and silt. The soil is most fertile and suitable for cultivation of high yielding crops like sugarcane and wheat.
 - 2) Inceptisols: Calcareous alluvial soils occur mostly in the central part and locally known as Mathivari. The percentage of both phosphoric acid and potash are higher in this region. This soil is richer in lime content and kanker than Balsundari soil. This forms the typical paddy land of Bihar.

4.3 GEOMORPHOLOGY

The Bihar state can be broadly subdivided into three major unit's i.e., main physical subdivisions is the Northern Mountains, the Gangetic Plains and the Central Highlands. Northern Mountains comprises the Himalayan ranges including their foot hills. The Gangetic plains, situated between the Himalayas and the Deccan plateau constitute the most fertile plains of the subbasin ideally suited for intensive cultivation. The Central highlands lying to the south of the Great plains consists of mountains, hills and plateaus intersected by valleys and river plains. They are largely covered by forests. Aravali uplands, Bundelkhand upland, Malwa plateau, Vindhyan and Narmada valley lie in the region. Predominant soil types found in the subbasin are sandy, loamy, clay and their combinations such as sandy loam, loam, silty clay loam and loamy sand soils.

Geomorphologically the area may be divided into (i) Pediplain, (ii) Ridges and Valleys (iii) Flood plain and (iv) Terraced alluvial plain. The elevation of gently sloping pediplain varies from 100 m to 75 m above m.s.l. The Sone and Punpun are the two major rivers flowing through the western part of the district.

The district comprises extensive plain formed by the alluvium brought by the Ganga, the Gandak and distributaries of Gandak. The morphology of the area has been shaped mainly by Gandak river which originates in the Himalayas in Nepal. Morphologically it can be classified into three broad categories.

- 1) Hazipur Surface: It is the oldest morpho-unit of the area comprising yellow-brown to brownish-grey compact clay.
- 2) Vaishali Surface: It overlies the Hazipur surface. This surface comprises ash-grey-silt/silt-clay/clayey-silt and has been found development on the eroded and very gently sloping Hazipur surface.
- 3) Diara Surface: It is the lowest and youngest geomorphic unit which emerges from river bed. The diara surface has come into existence after the

4.5 FOREST

There is no forest in Vaishali district of Bihar


4.6 VEGETATION:

There is no vegetation in the proposed area.

4.7 SOILS

The district is an extensive plain formed by the rich alluvial soil brought down by several rivers and streams Soil/Earth is unanimously spread over the area. inceptisols and entisols are major soil in the district. There is no need of prospecting work. As mentioned, the thickness of top soil is considered up to 0.15 m. The depth of suitable earth excavation is considered 2 m bgl. Earth mining is being proposed up to a short depth of 2 m from the surface level. Once soil removed, no excavation will be carried in future. Hence, no need of a proposal of future prospecting.

प्रस्तावित क्षेत्र



4.8 MINERAL RESERVES

Earth reserves have been estimated as per the standard procedures. The area of mining land is around **3.38 Ha.** and the **average thickness of mineral (2 m)** are multiplied to get the volume. 10% area wise left for 1 m wide berm all along the periphery of mining land to get the available for actual mining. About 10% mining losses reserves blocked due to slope has been considered to get the mineable quantity. Detail of calculation is given ahead:

Mauza	Area in Ha	Area in Sq. m	Max ^m depth (m)	Area of Berm left (10%)	Area Considered for Mining in Sq. m	Top soil in cubic meter	Reserves In cubic meter	
							Geological reserve	Mineable reserve
Pahetiya	3.38	33800	2	3380	30420	5070	67600	56277
Total	3.38	33800	2	3380	30420	5070	67600	56277

4.9 CLASSIFICATION OF RESERVES

All the quantity estimated as above is considered under proved (111 category under UNFC classification) category

UNFC is a three-digit code-based system, the Economic viability axis representing the first digit, the Feasibility axis the second digit and the Geologic axis the third digit. The three categories of Economic viability have codes 1, 2 and 3 in decreasing order; similarly, the three categories of Feasibility viability have also codes 1, 2 and 3 while the four stages of geological assessment are represented by four codes i.e., 1 (detailed exploration), 2 (general exploration), 3 (prospecting) and 4 (reconnaissance). Thus, the highest category of resources under UNFC system has the code (111) and for lowest category the code is (334).

40. GEOLOGICAL RESERVES

Particulars	Unit	
Total Area available for mining (As per document)	33800	Sq.m
Average Thickness considered	2	M
Total Volume of Mineral (Earth)	67600	Cum
Total Geological Reserves (Earth)	67600	Cum

4.11 MINEABLE RESERVES

Particulars	Unit	
Total Area available for mining (As per document)	33800	Sq.m
Peripheral Strip Area (Area wise 10% of total area)	3380	Sq. m
Minable area	3420	Sq. m
Thickness of top soil	0.15	M
Total top soil	5070	Cum
Average Thickness considered for mining	1.85	M
Total Mineable Reserves	56277	Cum
Maximum production proposed	56,277	Cum
	In tones (volume x 1.53 ton/m ³)	86,104 Tons

The geological reserves have been for individual block. Geological reserves have been completed through cross sectional area method. The area of each section line is multiplied by strike influence to get the volume.

4.12 LIFE OF MINE

Life of mine is up to **1 year**. During this period **56277 cum** of earth shall be excavated and use for land filling work (Commercial) which require prior environment clearance.

श्रीकांत कुमार



CHAPTER – 5

MINES & MINING METHOD

5.0 MINING

Mining will be done as per the guideline of **Bihar Mineral (Concession, prevention of illegal mining, Transportation & Storage) Rules, 2019**

- This is an open-cast mining project. The operation will be carried semi- mechanized. The earth/soil will be collected in its existing form.
- Mining will be carried out only up to depth of 2 m bgl of above ground water level (whatever is less).
- No drilling/ blasting is required as the material is loose in nature
- Proper benching of 1 m height and 6-meter width will be maintained for mining block as per guideline M.M.R.-1961, under rule, 106.
- Mining will be done only during the day time and completely stopped during the monsoon period.

5.1 RESTRICTION ON MINING

- I. The activity associated with mining / excavation of brick earth and ordinary clay / earth for purpose of brick manufacturing, construction of roads, embankments etc. shall not involve blasting.
- II. The mining / excavation activity shall be restricted to a maximum depth of 3m below normal ground level at the site.
- III. The mining / excavation activity shall be kept above the ground water table at the site.
- IV. The mining / excavation activity should not alter the natural drainage pattern of the area.
- V. The mined/ excavated pit shall be restored by the project proponent for useful purpose(s).
- VI. Appropriate fencing all around the mined / excavated pit shall be made to prevent any mishap.
- VII. Measures shall be taken to prevent dust emission by covering of mined /excavated earth during transportation.
- VIII. Safeguard shall be adopted against health risks on account of breeding of vectors in the water bodies created due to mining/ excavation of earth.
- IX. Workers / laborers shall be provided with facilities for drinking water and sanitation.
- X. A berm shall be left from the boundary of adjoining field having a width equal to at least half the depth of proposed excavation.
- XI. A minimum distance of 15 m from any civil structure shall be kept from the periphery of any excavation area.
- XII. No mining of earth / excavation of 'brick earth' or ordinary earth shall be permitted in case the area of mining excavation is within 1km of boundary of national parks and wild life sanctuaries:

5.2 PROPOSEED METHOD OF MINING

The Mining will be carried out as per new minor mineral policy by Bihar Government. Only dry soil will be transported.

- Excavation of soil/ earth will be done open cast semi- mechanized method.
- No OB/ waste material will be produced at the mining site. The earth shall be exploited up to depth of 2 meter only through the formation of bench height 1 meter & width 6 meters. An approach road having width 6 meters and gradient 1:12 shall be provided for the movement of loaded machineries & transportation of earth. Earth/Soil shall be exploited through semi-mechanized tool & filled into tractors /Trucks and transported to road development site.
- No drilling/ blasting are required as the material is loose in nature.
- Proper benching of 1 m height will be maintained.
- Roads will be properly made and sprayed by water for suppression of dust.
- Roads in the lease area for the movement of loaded trippers/ trucks will not have slopes more than 1 in 16.

Handwritten signature



5.3 TRANSPORTATION PLAN

Dumper/Truck: -

- ✓ Every dumper /tractor will be provided with efficient brakes.
- ✓ Efficient audible warning devices will be provided with the vehicle.
- ✓ Every dumper /tractor will be under the charge of a competent person, authorized in writing by the manager.
- ✓ No person, other than the driver or his helper, if any, will ride on a dumper /tractor.
- ✓ No person will be permitted to ride in the running board of a dumper /tractor.
- ✓ The loaded dumpers /tractors will not be reversed on gradients.
- ✓ Sufficient stop blocks will be provided at every tipping point and these will be used on every occasion when material is dumped.
- ✓ Standard traffic rules shall be adopted and followed during movement of all dumpers /tractors.
- ✓ They shall be prominently displayed at relevant places in the opencast workings.
- ✓ When not in use, every dumper will be moved to and stood on proper parking places.
- ✓ No person will be permitted to work on a chassis of a dumpers /tractors, with the body in rest position, until after the dumpers /tractors body has been securely blocked-in position.
- ✓ No unauthorized person will be permitted to enter or remain in any turning points.
- ✓ While inflating tyres, suitable protective cages shall be used.
- ✓ Tyres will never be inflated by sitting either in the front or on the top of the same.
- ✓ While the vehicle is being loaded / unloaded on gradient, the same will be secured stationary by the parking brake, and other means suitably designed stopper block, which could be placed below the tyres.
- ✓ At least once in every two weeks the brakes of every dumper will be tested as below: -

Service Brake test: - The brake will be tested on a specified gradient and speed when the vehicle is fully loaded. The vehicle should stop within the specified distance when the brake is applied.

Parking brake test: - The parking brake shall be capable to hold the vehicle when it is fully loaded and placed at the maximum gradient. Maximum gradient of the roadway which is permitted only for a period of at least 10 minutes.

A record of such test will be maintained in a bound paged book and will be signed by the competent person carrying out the test. These records will be countersigned by the engineer and manager.

All vehicles shall be tested and examined once at least in every 6 months.

A notice shall be displayed outside every vehicle that "No Unauthorized Travelling Allowed".

Duties of dumpers /tractors operators: -

At the commencement of every shift, the operator shall personally inspect and test the machine, paying special attention to the following details: -

- i. Tyre pressure, brakes, horn and the Lights are in working order.
- ii. The driver will neither take out the machine for work nor will he work the machine unless he is satisfied that it is mechanically shown and in efficient working order.
- iii. The driver will maintain a record of every inspection made in a bound paged book, kept for the purpose and shall sign every entry made therein.
- iv. The driver will keep the cab window clean so to ensure clear vision at all times.
- v. Driver will ensure that the gear is in neutral position before stopping the engine. He will park the vehicle
- vi. In reverse gear, on level roads and down gradients.
- vii. In low gear, on up gradients.
- viii. The driver will negotiate downhill gradients in low gear, so that minimum of braking is required.

Signature



- ix. The driver will not drive too fast, avoid distractions and drive defensively.
- x. Before crossing a road / railway line he will reduce his speed looking both directions along the road or railway line and will proceed across the road or line only if it is safe to do so.
- xi. The driver will not operate the dumper in reverse unless he has a clear view of the area behind the vehicle.
- xii. The driver will see that the vehicle is not overloaded.
- xiii. The material is not loaded in a dumper so as to project horizontally beyond the sides of its body.
- xiv. The driver will not allow any unauthorized person to ride on the vehicle.
- xv. When there is a poor visibility, the speed of a vehicle will be restricted in a manner that the braking distance is maintained shorter the distance of visibility.
- xvi. The driver will not leave his machine during the shift. When he finishes his work, he will hand over the machine to his reliever or lock the excavator's cab.

Model traffic rules: -

Rule 1: Procedure

- a. No person will drive or operate a vehicle in or about the mine unless authorized to do so for that vehicle or class of vehicle by mines manager.
- b. A private vehicle will not be driven within the mine premises, unless authorized by mines manager.
- c. Any driver, not regularly working in or about the mine, will get permission to enter the mine premises from the mine manager, or an official of the mine authorized for the purpose, prior to driving a vehicle within the mine premises, which will be prominently delineated.

Rule 2: Speed Limits


- a. Permanent or temporary speed limits, set by the mine manager, for any area of the mine or any vehicle or class of a vehicle will be adhered to.
- b. Where visibility or road conditions are poor, a driver shall reduce the speed of his vehicle to the extent necessary to maintain effective control.

Rule 3: Right of Way (Traffic Management)

- a. At intersections, which are not controlled by traffic signs, all drivers should give way to the vehicle on the right, except as stated below: -
 - i. All drivers will give way to emergency vehicles showing a **flashing red light**.
 - ii. Vehicles being used for grading, rolling, watering and repair of roads have right of way over all vehicles except emergency vehicles. These vehicles will show an **amber flashing light**.
- b. The driver of a vehicle, having right of way over another vehicle, will not endanger himself or others through insistence on that right, if this is likely to cause a collision.

Rule 4: Parking and Standing

- a. A driver will not park or stand his vehicle in a position that will endanger other traffic on the mine premises.
- b. A driver will not park or stand a vehicle opposite another vehicle on haul road.
- c. A driver will not park or stand his vehicle within 30 meters of the working area of the mobile equipment, or where his vehicle cannot be clearly observed.
- d. A driver will not park or stand his vehicle within the area of swing of the dragline, without first obtaining permission from the operator.



- e. A driver, before leaving his vehicle, shall ensure that the vehicle is secure, that parking brakes have been applied, and that all implements have been lowered. If circumstances dictate that a heavy vehicle must be parked on a grade, then the wheels should be chocked, and the steering turned off centre.
- f. A driver of a vehicle will. Before moving from a parked position, ensure that its path is free of any obstruction and/ or personnel.
- g. A driver of a light vehicle will observe the following rules while parking his vehicle: -
 - ✓ Stop engine;
 - ✓ Leave vehicle in first or reverse gear;
 - ✓ Apply hand brake;
 - ✓ Not Park in front of or behind a heavy vehicle;
 - ✓ Not Park within 30 meters radius of a Shovel/ excavator;
 - ✓ Chock the wheels, if parked fencing is up or down a slope.

Rule 5: General

- (a) Vehicles will not be driven over electric cables, air hoses or water lines unless these are properly protected.
- (b) Seat belt will be provided for the operators' personnel safety. They are to be worn at all times while the vehicle is operating.
- (c) Passenger will not be carried on any vehicle, unless seated in approved seating, or where authorized for training purposes by the mine manager.
- (d) A caution signed or hazard lights are to be placed at the front and rear of any vehicle which is being towed, or which has been broken down and is obstructing the roadway.
- (e) Operators and drivers are responsible for cleanliness, oil and water checks, tyres, and fuel, for the machines and vehicles under their control.
- (f) Operators and drivers are responsible for ensuring that their vehicle is correctly illuminated during hours of darkness.
- (g) Headlights are to be dipped when approaching other traffic or mobile equipment in working areas.
- (h) All earth moving equipment will sound blast horn before moving off from parked position.
- (i) No smoking or naked lights are permitted during re- fuelling and the checking of batteries.
- (j) Dumpers are to be loaded in such a manner that spillage is minimized. Loads should be centralized to maximize stability. Loads, which have an excess of 1.2 meters, shall be clearly marked by a red flag during day and red light at night. All loads will be made secure for travel.
- (k) The driver will make sure that the vehicle has adequate clearance, particularly when reversing, parking, passing other vehicles and units, or passing stationary and static equipment.

Rule 6: Overtaking

- a. The driver of the vehicle may overtake any other vehicle with due caution, provided that
 - i. The speed limit is not exceeded.
 - ii. There is sufficient visibility of the road ahead.
 - iii. The vehicles are clear of any road intersection or junction.
- b. No overtaking will be permitted in the vicinity of road dividers.
- c. While driving behind the haul truck the driver will ensure that he is visible in the rear-view mirror until he puts off or overtake.

Rule 7: Signs

- a. All signs are to be obeyed.
- b. Temporary signs will be removed immediately after their need is over.



- c. Warning signs are to be noted at all times.

Rule 8: Mechanical condition of vehicles

- The drivers of each heavy vehicle in use will at least, daily examined his machine to ensure that it is in safe working order and make a written record of his observations of such examinations.
- The driver of any vehicle will report, to his supervisor, any defect in the vehicle as well as any damage to the vehicle are injury to himself arising out of a vehicle incident of the mine.

Traffic Study: -

The loaded & unloaded dumpers /tractors will move on the National Highway, SH or approach road for the further transportation of minerals from the lease area to other places of road development project.

Keeping in view that, the movement of dumpers /tractors may increase the traffic density of the nearest highway. A traffic Study on the present traffic scenario have been made to measure the increase PCU/hr.

5.6 EXTENTION OF MECHANIZATION

Machinery Requirement:

Machinery required for earth mining will be Back Hoe Loader and Tractor. Proposed Production of earth is 56277 cubic meter in 180 days i.e. **312 cum/day**

- Excavator & Back Hoe loader -2 for cutting and loading soil in tractor trollies
- Tracrtor-2 for transportation of soil to the dumping site(s).
- Dumpers-2, 9 CUM Capacity
- Water Tanker – 1 of capacity 5000 Lt. for sprinting of water on approach road & irrigation of plants

Type of Machinery		
SL NO	MACHINERY	NUMER OF MACHINERY
1	Excavator & Back Hoe Loader	2
2	Dumpers	2
3	Tractor	2
4	Water Tanker	1

Manpower Requirement:

Manpower required is as below table:

SL NO	DESIGNATION	NO OF PERSONS
1	Administrator cum supervisor	1
2	Back Hoe Loader Operator	1
3	Dumper Driver	2
4	Tractor Driver	3
5	General helper	6
TOTAL		13

Output Per Man Per Shift (OMS)

Total production in a day = 312 M³

Total Manpower = 13

Hence, output per man/shift (OMS) = $312/13 = 24 \text{ M}^3/\text{Man}$

Handwritten signature and initials



Diesel Consumption:

Sl. No	Machinery	Number of Machinery	Average Fuel Required/ Hour	Effective Production Hr./ Day	Total Fuel Consumption (Lt.)
1	Excavator & Back Hoe Loader	2	6	6	72
	Dumper	2	3	6	36
2	Tractor	2	1.5	6	18
3	Water Tanker	1	1.5	4	6
Total					132

So, Diesel consumption factor = $132 \text{ Lt.} / 312 = 0.42 \text{ Lt.}$

Hence Total Diesel Requirement for Project = $0.42 \times 56277 = 23636 \text{ LT}$

Daily Diesel requirement = 132 Lt.

Station 1-2 *Done*



CHAPTER -6

6.1 DRILLING AND BLASTING

No drilling and blasting are required in excavation of earth.

श्रीकांत ठुमल



CHAPTER-7

7.0 MINE DRAINAGE SYSTEM

7.1 BASIN/SUB-BASIN, DRAINAGE: -

The Vaishali district constitutes a part of Ganga River basin. It has two sub-basins, namely Gandak sub-basin and Burhi Gandak sub-basin. The major part of the district falls under Burhi Gandak sub-basin. The Gandak is the main river flowing in the south-easterly direction and forming western boundary of the district. It discharges in the river Ganga near Hajipur. The river Gandak does not receive any important tributary in its course. There are two important distributary channels namely the Gandaki and the Baya rivers flowing parallel to the river Gandak and discharge into the river Ganga. The Baya runs through the central part of the district in north-south direction.

7.2 HYDROLOGY

Quaternary Alluvial deposit consisting of alternate layers of sand, silt, clay, and gravel forms prolific unconfined and confined aquifer system. The unconfined aquifer system consists of sand layers with parting of thin clay layers up to a depth of 60-70 m. The clay layers at shallow depth are not regionally extensive as such the entire sequence behaves as unconfined aquifer system. The transmissivity of the aquifer varies from 1000 to 5000 m² /day. The specific yield varies between 8-12%. The movement of ground water is in south-east direction towards the river Ganga. The aquifer is highly potential. A yield of 50- 100 m³ /hr may be obtained from a well tapping 40 m thick aquifer for nominal drawdown.

Depth to ground water level during pre-monsoon and postmonsoons for the year 2011 indicates that water level is ranges from 7.15 to 8.90 m bgl and in post-monsoon its ranges between 3.68 to 6.06 m bgl.

Exploratory drillings down to depth range of 127 to 300.15 m by CGWB at Lalganj, Hazipur and Garoul confirm presence of highly potential and thick sand & gravel layers. The zones tapped at Kohnara ranges from 86 to 248 for a total drilled depth of 300 m and the zones tapped at Lalgang ranges from 141 to 220 meter for a total drilled depth of 240 m. Due to impervious clay layers at greater depth the aquifers are semi-confined to confined in nature. The storativity value of the deeper confined aquifer is 0.13×10^{-7} and transmissivity value ranges between 621 and 5163 m² /day. The piezometric head has been found to rest within 5 mbgl. A high discharge of more than 200 m³ /hr may be obtained from a well drilled to 300 m tapping sufficient thickness of confined aquifer.

7.3 GROUND WATER RESOURCES

Annually replenishable dynamic ground water resource of the unconfined aquifer has been estimated as on 31st march 2009 for all the blocks following GEC-1997 norm. The net annual replenishable ground water resource of the district is 71952 ham. The gross draft for all uses, (irrigation, domestic and industrial water supply) as on 31st March 2009, is 40288 ham. The allocation for 8 domestic and industrial requirements supply up to next 25 years is 8730 ham. The stage of ground water development of the district is 56%. Except the Rajapakar Block, all the fifteen blocks of district fall under safe category. The ground water can be further exploited for irrigation and other uses. Maximum ground water development is in Rajapakar block (74.7%), while minimum in Vaishali block (35.4%).

श्रीमान् जेम्स



CHAPTER-8

8.0 STACKING OF MINERAL REJECTS AND WASTE DISPOSAL ARRANGEMENTS

Brief description of the arrangements made for top soil mineral rejects and waste disposal including precautions taken in selection of disposal site (s) along with their respective quantity likely to be generated.

The mining activity is being carried out in leased location. Upper 0.15m thick layer of soil has been considered as top soil which will be kept on the berm safely.

This will be dumped temporarily on the berm or earmarked place near mine working and after removing Earth the top soil will be spread over the mined-out area to restore the proposed fields or used beside the place where plantation is to be done.

Atm 1st June



CHAPTER-9

9.0 ANTICIPATED ENVIRONMENTAL IMPACTS, MITIGATION MEASURES AND ENVIRONMENTAL MANAGEMENT PLAN

The pollution potential of the proposed project, its possible impacts on the surrounding environment during pre-operational and operational phases and the necessary management actions proposed for control and abatement of pollution are furnished hereunder.

9.1 AIR ENVIRONMENT

Mitigation Measures for Fugitive Dust Emission:

- ❖ Tractors will be covered by tarpaulin sheet to prevent dust emission.
- ❖ Water will be sprayed after loading activity (if soil would be in dry condition).
- ❖ The dust suppression measures like water spraying will be done on the haul roads and working areas.

For Vehicular Emission

- ❖ Overloading of tractors and trolleys will be prevented.
- ❖ Vehicular emission can pose serious health hazard. During the clay/soil mining extraction, tractor would be used for transportation. Tractor comprises of diesel engine produce particles are dangerously fine of PM_{10} & $PM_{2.5}$ it is known fact that combustion of diesel generates small particulate matter, nitrogen oxides and sulphur dioxide.
- ❖ Ultra low sulphur diesel would be used in vehicle. CPCB prescribed emission Standards for the vehicle would be followed

9.2 WATER ENVIRONMENT

Mitigation measure

- ❖ Safeguards will be adopted against health risks on account of breeding of vectors in the water bodies created due to borrowing/excavation of earth by sprinkling of pesticides.
- ❖ Labourers would not be allowed to through trashes in water bodies.
- ❖ Utmost care will be taken to minimize or control oil spills or leakage from vehicles used for earth transportation.
- ❖ The washing of tractors and trolleys on the land will be avoided.
- ❖ Water Quality Monitoring for the, ground water shall be carried out seasonally to ensure that the water quality is not affected by the project activities.
- ❖ The contractor will add here all guidelines and rules for proper and scientific method of mining during the period of extracting earth/clay. Thus, the project activities shall not have any adverse effect on the physical components of the environment and therefore may not have less effect on the recharge of ground waters or affect the water quality.

9.3 LAND ENVIRONMENT


Anticipated impact

The major impact of earth/ clay mining on land is changes in landscape, land stability and soil loss. Due to continued and unscientific clay mining, pits of different dimensions would be formed in the affected areas. Some of the pits may later be covered with water to form artificial ponds. The artificial ponds created in random location due to indiscriminate clay mining may lead to land stability problems in the adjoining areas. The problem of subsidence will be aggravated in areas where the subsurface geology is with sand and clay alternations. Other impacts on land include:

- ❖ Disposal of packing materials, carried by the workers. This packing material would include used sachet / gutka /pan masala pouches. Polythene/plastic bag are by used by the workers to bring their foods etc.

Mitigation measures

- ❖ *Top soil (0.15 m)* will be scooped first and stored for further reclamation of mined area. soil/earth mining will be limited to 2 m only from the surface.



- ❖ No foreign material like polythene/plastic bag, jute bag and useless articles should be allowed to remain / spill on the land, or no pits/pockets will be allowed to be filled with such material.
- ❖ Mining will not exceed beyond the agreed extraction depth.

9.4 NOISE ENVIRONMENT

Anticipated impacts

As far as noise pollution is concerned, clay mining does not contribute much to noise pollution, except the noise generated from the vehicles that transport raw clays scooped from lands and the products from the clay-based industrial units. Noise level in the working environment is compared with the standards prescribed by Central Pollution Control Board which has been adopted and enforced by the Govt. of India through The Noise Pollution (Regulation and Control) Rules, 2000.

Mitigation measures

- ❖ Well maintained vehicles will be used in order to reduce the noise during movement of vehicles.
- ❖ Regular and proper maintenance of transportation vehicles tractor will be ensured.
- ❖ There would be restriction on vehicular movement during night time.

9.5 BIOLOGICAL ENVIRONMENT

9.5.1 Impact on ecological factors

The area where earth /clay mining is practiced is usually barren and waste lands which are generally devoid of any natural vegetation. There will not be any impact on the biological environment in the surrounding area. There will not be any impact on the biological environment in the surrounding area.

9.6 GREENBELT DEVELOPMENT

It is proposed to have plantation on un-worked areas (lease periphery or berm of about 1m width) and along haul roads to provides cover against dust dissemination. Plantation will also be carried out as social forestry programmed in villages schools and the areas allocated by the Panchayat/ State Authorities. During plantation, local plant species will give preference or in consultation with local forest officials.


The proponent will plant about 50 saplings on the boundary/ berm.

9.7 TRIEES PROPOSED FOR AVENUE PLANTATION FOR GREEN BELT DEVELOPMENT

SI. No.	Agro climatic zone & Sub zone	Middle Genetic Plains, north west alluvial sub zone	
		Common Name	Pollution control feature
1	Acacia nilotica	Babul	Tolerant to SO ₂
2	Azadirachta indica	Neem	Tolerant to SO ₂
3	Pithecolibium ducele	Jungle jalebi	Tolerant to SO ₂ and Dust control
4	Mangifera indica	Aam	Tolerant to Dust control
5	Tectona grandis	Sagon	Tolerant to Dust control
6	Ficus benghalensis	Bargad	Tolerant to Dust control
7	Scigium cumuni	Jamun	To stop soil erosion
8	Terminalia arjuna	Arjun	To stop soil erosion
9	Populus eliate	Popular	Fast growing
10	Ficus religiosa	Peepal	Dust particles absorbance

9.8 SOCIO-ECONOMIC ENVIRONMENT

In the trade-off between the socio-economic needs and environmental conservation, generally cannot be takes the upper hand socio-economic condition of the project area, the activities cannot be ignored. As regard socio-economic condition of the project area, the earth/clay mining activity provides employment opportunities to various people. The economic base of the region will also be enhanced, if the mining is allowed. In the case of land use, it is clear that any type of quarrying would drastically change the existing land use.

Signature


The proponent will take care of all the facilities for workers at the mining site area.

- ❖ For sanitation purpose portable/mobile toilets will be provided by the proponent.
- ❖ Provision of drinking water: Water required for drinking purpose will be obtained through tankers/nearby sources with proper permission.

9.9 ENVIRONMENT MANAGEMENT PLAN

To mitigate the adverse impacts which are likely to be caused due to the mining operation and overall scientific development of local habitat, environmental management plan (EMP) has been formulated and integrated with the mine planning. Proper environmental management plan is proposed for 'Sandy Soil/Earth' mining project to initiate the impact during the mining operations.

- i. A berm will be left from the adjoining field having a width 1.0 meter (equal to at least half the depth of proposed excavation). Further plantation will be done above the berm.
- ii. No labour camps will be established on Mining site.
- iii. No cooking, or burning of wood will be allowed at the mine site.
- iv. Prior to commencement of mining, a short awareness program will be conducted for labours to make them aware of way of working and various precautions to be taken while at work. Such program will be repeated occasionally.
- v. No tree cutting, chopping, lumbering, uprooting of shrubs and herbs will be allowed.
- vi. Collection of air and water samples at strategic locations with frequency suggested and by analyzing thereof. If the parameters exceed the permissible tolerance limits, corrective regulation measure will be taken.
- vii. Collection of earth/ clay samples at strategic locations once in every year and analysis thereof with regard to deleterious constituents, if any.
- viii. Measurement of water level fluctuations in the nearby ponds dug wells and bore wells.
- ix. Plantation/a forestation will be done as program i.e. along mining lease, road sides and near civic amenities, which will be allotted by Government bodies. Post plantation, the area will be regularly monitored in every two years for evaluation of success rate. For selection of plant species local people should also be involved

9.10 RISK & HAZARDS MANAGEMENT

As it is soil/ earth mining project, so there are no major risk and hazard activities associated with the proposed activities. But the project proponent will must take care the site location by:

- ❖ Proper fencing all around the mining site so that it can prevent any mishap or accident in future.
- ❖ The materials being transported after excavation will be properly covered with tarpaulin sheet.
- ❖ Periodic water sprinkling will be done to arrest dust.

9.11 LAND RECLAMTION PLAN

Brief description of the reclamation plan giving the proposed plantation programme, scope of backfilling worked out pits.


As stated earlier that the total generated top soil will be kept safety on the berm of mining site. After removal of all the proposed quantity of Earth/clay, the top soil will be spread over the mined-out pit so that the fields can be used for agricultural activity.

9.12 STRATEGY FOR PROTECTION OF RIVER COURES, NALAS, WATER TANKS, VILLAGES, IMPORTANT MONUMENTS:

Briefly outlined the proposed strategies for protection of the following:

- a) River courses
- b) Nalas
- c) Water tanks
- d) Villages / houses / hutments / agricultural land

No nala or drainage passes within or near mining area. There are no important monuments and waters tanks nearby the mining area. Mining is confined in very small scale. Earth from proposed field will be mined out.



Upper top fertile of proposed field will be kept safely. After removal of earth from the area, safely kept top soil will be spread back on the mined-out field. Thus, the mined-out area will be used for agricultural activities in future.

9.13 SITE SERVICES

Working Office: Temporary working office will be maintained at site. This will be a temporary structure and can be easily shifted one side to another site as & when required. Safe drinking water will be kept in covered buckets / clay pitcher and will be provided to mine workers.

Rest Shelter: A temporary structure as a rest shelter to labours will be provided to the workers near mine site.

Primary Health/First Aid: First aid box with principal medicine will be kept at mine site to facilitate the first aid treatment to the workers.

Water arrangement: Water for drinking is required. Project Manager/authored leader will arrange a water tanker for the purpose. Separate arrangements for drinking water for the labours will be made in the working office.

Socio-Economic Benefits

Mining industry play an important role in economic sector in India. The region, where the project is situated, mostly people depend on agriculture. The important benefits accruing from the project to the state in the form of royalty can thus be stated as-boost to local and regional economy. The development of mining in the area provides direct and indirect employment opportunities, better infrastructural facilities, communication and socio-economic infrastructure.

9.14 WATER REQUIREMENT

Total water requirement for the project is 6KLD. Breakup details are as below-

Sl. No.	Purpose	Water requirement (KLD)
1.	Domestic Use	1
2.	Water Sprinkling	4
3.	Plantation	1

Amir BME



CHAPTER-10
MINE CLOSURE PLAN

10.0 Introduction:

Applicant Name & Full address	M/s Aayushman Enterprises Prop- Mr. Shrikant Kumar S/o Ramdas Ray At- Garha, Block-Bochaha , Muzaffarpur, Bihar-843103			
Contact No. & E-mail ID	Mob: +91-9135603592 Email ID:			
Status of Lessee:	Individual/Proprietorship			
Location:	Mauza- Pahetiya, Block- Hajipur, District- Vaishali (Bihar)			
	Thana No.	Khata No.	Khesra No.	Area (acres)
	60	372, 139, 63 & 358	280, 281, 283, 282, 284 & 287	3.38
	Total			3.38
Extent of Lease area	3.38 hectare			
Type of Lease	Non- Forest Land			
Present Land use pattern	Non-Forest Land			
Present method of Mining and mineral processing	refer Chapter No.- 5			

10.1. Reasons for Closure:

The mineral soil/ earth will be excavated for use of land filling at road development project site. After completion of excavation of mineral up to depth of 2 m, the mine will be closed as per rules, regulations and orders. No premature closure is anticipated.

10.2. Statutory Obligations:

As per rule 17 (7) of Bihar Minerals (Concession, Prevention of Illegal Mining, Transportation & Storage) Rules, 2019, 22 of amended rules of BMMC Rules 2014 & 23 B of MCDR 1988 for every fresh grant of mining lease a progressive mine closure plan is required to be submitted in compliance of the aforesaid rule of MCDR 1988, the mine closure plan is being in accordance with the guidelines issued by Chief Controller of Mines (CCOM) vide circular no. 14/2003.

10.3. Closure plan preparation:

a). Name and address of the Applicant:

Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, Block-Bochaha ,
Muzaffarpur, Bihar-843103

b). Name & address of R.Q.P.:

M/s Praneja Envirocare & Management Private Limited
Admn Off: Ground Floor, Opp. Vamika Apartment,
Near Passport Office, Ashiyana, Khajpura,
Patna-800014 (Bihar)
Mob: +91-9708251824, 9308014108
Email Id: pemanagementindia@gmail.com

c). Name of the executing agency:

M/s Aayushman Enterprises

Shrikant Kumar



The lessee himself shall execute the provisions of mine closure plan.

10.4	Mine Description:	
10.4.1	Geology and Exploration	Given at Chapter -4
10.4.2	Physiography	
10.4.3	Regional Geology	
10.4.4	Local Geology	
10.4.5	Exploration	
10.4.6	Estimation of Reserves	Given at Chapter -5
10.4.7	Proposed Mining Method	

10.5. Review of implementation of Mining Plan/scheme of mining including mine closure plan up to the final closure of mine:

Not applicable.

10.6. CLOSURE PLAN:

10.6.1 Mined out land:

In general, the environmental impact will always be adverse, due to mining operations if proper abatement measures will not be taken. The magnitude and significance of the environmental pollution caused by mining depends on type of mineral, method of mining and beneficiation etc. As a result of mining operation, the original ground profile will be altered. No proposal can be given for concurrent back-filling. Top soil is proposed to be spread over mined out areas so that it can be reused for agriculture proposes.

Land Use Pattern

Non-Forest Land

10.6.2. Water Quality Management:

Activity is limited up to 2 m below the ground level only and above the Water table. Thus, change in Ground water quality does not anticipate.

10.6.3. Air Quality Management:

Activity is limited. Any change in air quality does not anticipate. If required water sprinkling will be done regularly on haul roads. Vehicles are covered with tarpaulin sheets during transportation.

10.6.4. Waste Management:

For sanitation purpose portable/mobile toilets will be provided by the proponent. No cooking, or burning of wood will be allowed at the mine site and Labourers would not be allowed to through trashes in water bodies. Details are in **Chapter-9**

10.6.5. Tailing Dam Management:

Not applicable.


10.6.6. Infrastructure:

The proposed area is well connected with tehsil and district head quarter by all weather roads where all facilities are available. The proponent will have his own facility soon after start of excavation.

10.6.7. Disposal of Mining Machinery:

No specific immovable mining machinery is used in the excavation of soil/earth. It will be a semi-mechanized mine.

10.6.8. Safety and Security:



The proponent will follow all the rules and regulations as per provision of DGMS for safety and security of the proposed mine. To prevent access to the surface opening or excavated area from cattle's and local people the proponent will arrange security both by fencing or any other manner round the clock.

10.07. Disaster Management and Risk Assessment:

The proposed area is small. Activity is limited up to 2 m depth below ground level and final pit slopes will be kept 45°, hence chances of land slide, subsidence etc. is nil. **The proposed site falls in Seismic zone-IV.**

10.08. Care and Maintenance during Temporary Discontinuance:

During such time the time will be protectively fenced and staff will be employed for care and maintenance. As well as all the precaution laid down in the statute during temporary discontinuance will be maintained and followed.

10.09. Economic Repercussions of Closure of mine and manpower retrenchments:

It is not inferred to discuss economic repercussions of closure of mine and manpower retrenchment at this stage.

10.10. Time Scheduling for abandonment:

There is no proposal for abandonment of mine or initiating closure operations during the mine plan period, so question of abandonment does not arise. The time scheduling for abandonment in mining of earth will be after completion of excavation of mineral up to depth of 2 m only.

10.11. Abandonment Cost:

It is very difficult to estimate the actual abandonment cost at this stage. The applicant / Proponent is bound to comply the provision laid down under rules, regulations, acts, and order made by the centre or state government, statutory organization, court etc.

10.12. Any other information:

The lessee also intends to spend some amount towards community service. The figures are tentative and are subject to generation of profit. Around of 5% of the profit will be diverted towards this activity.

10.13. Financial Assurance:

The applicant shall comply the provisions for financial assurance as per rule of Bihar Minerals (Concession, Prevention of Illegal Mining and Transportation & Storage) Rules, 2019. However, it is not possible to calculate financial assurance at this stage.

12.14. Certificate:

The required Certificates are annexed separately and enclosed with the Mining Plan.

12.15. Plans, Sections etc.:

All the plans and sections are enclosed with the Mining Plan.

Date:

Place:

Praneja Envirocare & Management Pvt. Ltd.
RQP/SL No. 2011/10 2025/11 DT 07/11/2012

Authorized Signatory/RQP

Praneja Envirocare & Management Pvt. Ltd.

RULES & NOTIFICATION

No. L-11011/47/2011-IA.II(M)
Government of India
Ministry of Environment & Forests

Paryavaran Bhawan,
C.G.O. Complex, Lodhi Road,
New Delhi-110003.

Dated: 24th June, 2013

OFFICE MEMORANDUM

Subject: Guidelines for consideration of proposals for grant of environmental clearance under EIA Notification, 2006 for mining of 'brick earth' and 'ordinary earth' having lease area less than 5 ha – regarding categorization as Category 'B2'

The Hon'ble Supreme Court, vide its order dated 27.02.2012 in I.A.No.12-13 of 2011 in SLP (C) No.19628-19629 of 2009 titled Deepak Kumar etc. Vs. State of Haryana & Ors. has inter alia ordered that leases of minor mineral including their renewal for an area less than 5 ha be granted by the State / Union Territory only after getting environment clearance (EC) from the Ministry of Environment & Forests (MoEF). In order to ensure compliance of the aforesaid order of the Hon'ble Supreme Court, MoEF issued an OM No.L-11011/47/2011-IA.II(M) dated 18.05.2012 stating inter alia that all mining projects of minor minerals including their renewal, irrespective of the size of the lease would henceforth require prior EC and that the projects of minor minerals with lease area less than 5 ha would be treated as Category "B" as defined in EIA Notification, 2006 and will be considered by the respective State Environment Impact Assessment Authorities (SEIAAs) notified by MoEF and following the procedure prescribed under the EIA Notification, 2006.

2. MoEF has received a number of representations conveying problems being faced by the brick kiln manufacturers in obtaining EC for 'brick earth' mined by them for making bricks and by the developers of road projects in respect of mining of 'ordinary earth' used for road construction. The brick kiln manufacturers have requested that as the digging of 'brick earth' for making bricks is a small scale activity requiring digging only upto a certain depth, the activity may be kept outside the purview of EC. The project proponents developing roads have represented that the 'ordinary earth' required for road construction is generally taken from the farmers / individuals along the road alignment from their borrows. It would be impractical to ask the farmers / individuals to obtain EC for such digging. In a nutshell, the arguments being put forth are that while digging of 'brick earth' for brick making and 'ordinary earth' for road making do not have serious environmental implications, the provisioning for EC for such operations is impeding these development activities because of practical problems in obtaining EC.

Page 1 of 3



3. MoEF vide OM No.F.No.J-11013/12/2013-IA-II(I) dated 30.01.13 has constituted an Expert Committee, under the Chairmanship of Director, NEERI, Nagpur, to categorize Category "B" projects / activities into Category "B1" and "B2" under EIA Notification, 2006 and review classification of projects / activities into "A" and "B" and General conditions as contained in the aforesaid Notification. The issues raised by brick kiln manufacturers regarding 'brick earth' and road developers in respect of 'ordinary earth' were referred by MoEF to this Expert Committee to give their recommendations. The Committee deliberated upon these issues and has since given its recommendations in the matter.

4. The recommendations of the Committee have been examined by MoEF and the following has been decided:

(a) The activities of borrowing / excavation of 'brick earth' and 'ordinary earth', upto an area less than 5 ha, may be categorized under 'B2' Category subject to the following guidelines in terms of the provisions under '7.1 Stage(1)-Screening' of EIA Notification, 2006:

- (i) The activity associated with borrowing/excavation of 'brick earth' and 'ordinary earth' for purpose of brick manufacturing, construction of roads, embankments etc. shall not involve blasting
- (ii) The borrowing/excavation activity shall be restricted to a maximum depth of 2 m below general ground level at the site.
- (iii) The borrowing/excavation activity shall be restricted to 2 m above the ground water table at the site.
- (iv) The borrowing/excavation activity shall not alter the natural drainage pattern of the area.
- (v) The borrowed/excavated pit shall be restored by the project proponent for useful purpose(s).
- (vi) Appropriate fencing all around the borrowed/excavated pit shall be made to prevent any mishap.
- (vii) Measures shall be taken to prevent dust emission by covering of borrowed/excavated earth during transportation.
- (viii) Safeguards shall be adopted against health risks on account of breeding of vectors in the water bodies created due to borrowing/excavation of earth.
- (ix) Workers / labourers shall be provided with facilities for drinking water and sanitation.
- (x) A berm shall be left from the boundary of adjoining field having a width equal to at least half the depth of proposed excavation.

(xi) A minimum distance of 15 m from any civil structure shall be kept from the periphery of any excavation area.

(xii) The concerned SEIAA while considering granting environmental clearance for such activity for brick earth / ordinary earth will prescribe the guidelines as stated at (i) to (xi) above and specify that the clearance so granted shall be liable to be cancelled in case of any violation of above guidelines.

(b) Notwithstanding what has been stated at (a) above, the following will apply:-

- (i) No borrowing of earth / excavation of 'brick earth' or 'ordinary earth' shall be permitted in case the area of borrowing/ excavation is within 1 km of boundary of national parks and wild life sanctuaries.
- (ii) In case the area of borrowing / excavation is likely to result into a cluster situation i.e. if the periphery of one borrow area is less than 500 m from the periphery of another borrow area and the total borrow area equals or exceeds 5 ha, the activity shall become Category 'B1' Project under the EIA Notification, 2006. In such a case, mining operations in any of the borrow areas in the cluster will be allowed only if the environmental clearance has been obtained in respect of the cluster.

This issues with the approval of the Competent Authority.


(Dr. Saroj)
Director

Telefax : 24364067


To

1. All the Officers of IA Division
2. Chairpersons/Member Secretaries of all the SEIAAs/SEACs
3. Chairman, CPCB
4. Chairpersons / Member Secretaries of all the SPCBs/UTPCCs

Copy to:-

1. PS to MEF
2. PPS to Secretary(E&F)
3. PPS to ADG(F)
4. PPS to ADG(WL)
5. PPS to JS(AT)
6. PPS to IG(FC)
7. Website, MoEF
6. Guard File

Page 3 of 3





बिहार राज्यातर्गत लघु खनिजों के खनन योजना तैयार करने हेतु एंजेंसी Empanelment के लिए आमंत्रित Expression of Interest के तहत प्राप्त निविदा के क्रम में दिनांक-22.08.2019 को अपराह्न 03:00 बजे विभागीय समिति के बैठक की कार्यवाही :-

बिहार राज्यान्तर्गत लघु खनिजों के खनन योजना तैयार करने हेतु एंजेंसी Empanelment के लिए आमंत्रित Expression of Interest के दस्तावेजों/कागजातों के आधार पर PMU द्वारा तैयार विवरणी की जाँच खान एवं भूतत्व विभाग, पटना के अपर सचिव-सह-निदेशक-सह-अध्यक्ष के कार्यालय कक्ष में अन्य सदस्यों के समक्ष की गई।


2. आमंत्रित Expression of Interest के तहत कुल 36 आवेदन विभाग को प्राप्त हुए, जिसमें से कंडिका-14 में उल्लेखित प्रतिष्ठान भूमि इन्वॉयरटेक प्रा0 लि0 को योग्यता संबंधी प्रमाण पत्र नहीं संलग्न करने के कारण तथा कंडिका-34 में उल्लेखित मेसर्स संयुक्त इन्फ्रा को संबंधित योग्यता प्रमाण पत्र संलग्न नहीं होने के कारण अयोग्य घोषित करने का निर्णय लिया गया तथा शेष 34 को Empanelled करने का निर्णय लिया गया, विवरणी निम्नवत है :-

Sl. No.	Name	Contact Number	Qualifications	Rate for preparation of Mining Plan (per Ha)	Rate details	Address
1	Dr. Radha Nand Singh	9430252322 8340280122	M.Sc. Geology	Rs. 15,000/- (including of Tax & GST)		Dr. R.N Singh, 7HF- 6-20, Sector 7, Block 6, Flat 20, HIG Flat, Bahardurpur Housing Colony, Patna -800026
2	Shiva Test House	7903157774	M.Sc. Geology	Rate Slab attached	Rs. 10,000/- each Ha. Rs. 8,000/- for each subsequent additional Ha. (above rates are inclusive of 18% GST)	122 C, Aastha , Road No. 5 A, Patliputra Colony, Patna - 800013
3	Dr. Amarjeet Kumar Singh	9431508228	Ph.D(Geology)	Rs. 20,000/- GST will be charged as per Government rules		S/O-Udho Singh, C/O-- Sri Indrajit Kumar Singh, At & Po Jiradei; District-Siwan, Bihar-- 841245
4	Rajesh Kumar	8008802447	B.E. (Mining Engineer)	Rate Slab attached	Minimum INR 25,000/- per mining plan upto 3 Hectare. For more than 3 Hectare the rate shall be increase @INR 10,000/- per Hectare.	Plot No.87, Rajwara Building, Sikhar More , Near Mehta Petrol Pump, Manpur, Gaya- 823003
5	Dr. Abdul Rahman	7870527271	Ph.D In Geology	Rs. 8,000/- (inclusive of Taxes)		B-78, P.C. Colony, kankarbagh, Patna -800020
6	Punit Lala Mahto	9911537948 8709005622	M.Sc. (Geology)	Rs. 11,800/-	Rate per Hectare @10,000/- + GST @18% (Rs. 1800) =Rs. 11,800/-	House No.- 121, raghav Bhawan, kobibari, Sikandarpur, Bhagalpur - 812005
7	Sanjay Kumar	943106886	M.Sc. (Geology)	Rs. 25,000/-	Negotiable	Vastu-Sarita Colony, Janakpuri, Near -St. Karen's School, Gola Road, Danapur, Patna
8	Er. Navin Kumar Sinha	7366973516	B.E. (Mining)	Rs. 10,000/-		Er. Navin Kumar sinha, A-112, Sanjay Gandhi Nagar, Kali Mandir, Road No.-9, Patna, Bihar

श्रीमान 8000



9	Dr. Ashish Sharma	9753385659	Ph.D(Geology)	As per approved rate of Govt. of Bihar		Hasib Villa Naya Tola Line Bazar, Purnea, Bihar-854301									
10	Md. Sadique Alam	7091510996	M.Tech (Environmental Science & Engineering)	As per approved rate of Govt. of Bihar		Flat No-01 Ground Floor, hasib villa, Naya Tola Near Shiv Mandir, Line Bazar Purnea-854301									
11	Dr. Rakesh Kumar Singh	8085379660	Ph. D. (Coal Geology) M. Sc (Geology)	As per approved rate of Govt. of Bihar		Village- Chuppepur, P.O. - Belawa (Pindra), District- varanasi, (U.P), 221206									
12	Shailesh Kumar Singh	9431496906	M.Sc.(Applied Geology) M.Sc. Tech (Remote Sensing)	Rs. 25,000/-		B-8, Prachi Kanishka Apartment, bazaar Samitee Road, PO- Rajendra Nagar, District- Patna, Bihar-16									
13	Anecon Lab Pvt. Ltd.	9372404924	B.E Computer Science & Engineering	Rs. 31,860/-	Rate per Hectare @27,000/- + GST @18% (Rs. 4860) =Rs. 31,860/-	60, Bajiprabhu Nagar, Nagpur-440033									
14	Bhoomi Envirotech Pvt. Ltd.	9595773278	Required qualification not attached	Rate provided as per slab	a. For 0 to 2 Ha - Rs. 38,000/- b. For above 2.0 Ha to 5.0 Ha - Rs. 38,000/- c. Above 5.0 Ha - Rs. 28,000/- *All rates are per Hectare or part thereof. (Example - rate of 1.50 Ha shall be considered as 2.0 Ha	C/O Veena Gupta W/F Upendra Gupta, Shop No. 191, Plot No. 529, Golabazar, Nawadih Road, Near Kali Club, Aurangabad Bihar-824101									
15	Sens Geomine Consultancy Pvt. Ltd.	8235816865	M. Sc (Geology)	Rs. 15,000/- (exclusive of all GST & Taxes)		Kali Mandir Road, Opposite Puja Tent Service, Post-PS- Doranda, Ranchi-834002, Jharkhand									
16	Mohan S. Bhagwat	9868840983	M.Sc.Tech(Applied Geology)	Rs. 10,620/-	Rate per Hectare @9,000/- + GST @18% (Rs. 1620) =Rs. 10,620/-	Mahavir Sadan, Opposite litera Valley, Baudh Vihar Colony, Naya Tola, Kumhar-800026									
17	Eclipto India Pvt. Ltd.	7678639396	Required Qualification of the employees attached	Rate as per the slab provided	<table><tr><td></td><td>Per Ha. Rate (upto 5 Ha)</td><td>Per Ha. Rate (more than 10 Ha)</td></tr><tr><td>Rate upto 5 Ha</td><td>Rs. 10,000/-</td><td>Rs. 10,000/-</td></tr><tr><td>Rate more than 5 Ha</td><td>NA</td><td>Rs. 5,000/-</td></tr></table> * Rate is inclusive of GST and other applicable Taxes		Per Ha. Rate (upto 5 Ha)	Per Ha. Rate (more than 10 Ha)	Rate upto 5 Ha	Rs. 10,000/-	Rs. 10,000/-	Rate more than 5 Ha	NA	Rs. 5,000/-	C/O Kapilmuni Pathak, Shivapuram Road -2, Rukanpura, Bailey Road, Patna - 800014
	Per Ha. Rate (upto 5 Ha)	Per Ha. Rate (more than 10 Ha)													
Rate upto 5 Ha	Rs. 10,000/-	Rs. 10,000/-													
Rate more than 5 Ha	NA	Rs. 5,000/-													
18	Ravi Shankar	7485090640	B.E. (Mining)	Rate as per the slab provided	(a) Rs. 50,000/- per mining plan upto 5 Ha (b) for above 5 Ha area rate will be charged 6000/- per Ha additionally extra and above to 5 Ha upto 25 Ha (c) Rs. 2,00,000/- per mining plan for area of 25 Ha and will be charged additionally Rs. 3000/- per Ha extra and above to 25 Ha upto 50 Ha. (d) Rs. 3,00,000/- per mining plan for area of 50 Ha and will be charged additionally Rs. 2000/- per Ha extra and above to 50 Ha upto 50 Ha.	Village- Nagain, P.O.- Deohra, P.S.- Goh, Dist.- Aurangabad (Bihar) - 824114									
19	Indus Mining & Environment Consultancy	7542949027	B.E.(Mining)	Rs. 2,000/- per Hectare (Each Block Mining Plan - Rs. 30,000/-)		Indus Mining And Environmental Consultancy, 201, 2nd Floor, Mangal Market, Raja Bazar, Baily Road, Patna-14									



20	Pravin Kumar Sinha	7542949027	B.E (Mining)	Rs. 2,000/- per Hectare (Each Block Mining Plan - Rs. 30,000/-)		201,2nd Floor,Mangal Market,Raja Bazar, bailey Road, Patna-14
21	Md. Tauseef Warsi Greenera Mining & Envirotech Pvt. Ltd.	9534027112	M.Sc. (Geology)	Rs. 5,000/- (Excluding GST)		Greenera Mining & Envirotech Pvt.Ltd.,205 Mangal Market,Raja Bazar,Bailey Road Patna-800014
22	Prabhat Kumar Srivastava	8827477206	B.E(Mining)	Rs. 8,000/-		Flat No-101, Road No.-01, Boodh Nagar, Chiriy Tard, Postal Park , Patna-800001
23	Ashok Kumar Singh	8766859804	Mining Engineer	Rs. 8,000/-		C/o Shri Ram Prasad Singh, Mohalla - Mogal Kuan, P.O. - Sohsarai, P.S. - Sohsarai, Dist.- Nalanda, Bihar- 803118
24	Sandeep Kumar	8126253120	M.Sc. (Applied Geology)	Rs. 10,000/-		Anpurna Bhavan , C/O Ravi Kishan, Sundar Nagar, Lohia Path , Jagdeo Path , Patna - 800014 (Bihar)
25	United Exploration India Pvt. Ltd.	9431208782 9934304369	Required Qualification of the employees attached	Rs. 5,200/- (Inclusive all Taxes)		301,2nd Floor ,Sahid Rajendra Singh Complex,Anishabad , Patna-800002
26	Rian Enviro Pvt. Ltd	9431289638	Required Qualification of the employees attached	Rs. 5,000/- (Inclusive all Taxes)		202,2nd Floor,Mangal Market,Raja Bazar,Sheikhpura Patna -800014
27	Ascenso Enviro Pvt. Ltd.	9204207920	Required Qualification of the employees attached	Rs. 4,750/- (Inclusive all Taxes)		401,4th Floor ,Mangal Market,Raja Bazar,Sheikhpura,Patna-800014
28	M/s Baghel Environment & Waste Management Pvt. Ltd.	9431042532	Qualifications of candidates are attached	As decided by the department of Mines & Geology, Govt. of Bihar		Baghel Environment & Waste Management Pvt. Ltd. ,1st Floor, 27, Guru Sahay Lal Nagar, Road No. 2, Magistrate Colony, Ashiyana Nagar, Patna - 800025, Bihar
29	Gramin Lok Seva	9934452711	Qualifications of candidates are attached	Rs. 7,000/-	Note - 1. Minimum rate for a Sand Block - INR 25,000/- 2. Maximum rate for a Sand Block - INR 60,000/- OR As decided by the Department of Mines & Geology, Govt. of Bihar	27, Guru Sahay Lal Nagar, Magistrate Colony, Ashiyana nagar, patna- 800025, Bihar
30	Praneja Envirocare & Management Pvt. Ltd.	9708251824	Qualifications of candidates are attached	Rs. 10,000/- (Excluding GST @18%)	Remarks - Fee should not be less than 20,000 or more than 50,000 thousand for single block. (Excluded GST) OR As decided by the Department of Mines & Geology, Govt. of Bihar	103, Bhagwati kunj apartment, Road No. - 3D, Anand vihar Colony, Rukanpura, Patna (Bihar)- 800014
31	Institute of Environment and Eco Development	7004620817	Details Of Qualification Attached	Rs. 10,000/- (Excluding GST)	Rate will be negotiable as per direction from Department of Mines & Geology, Govt. of Bihar	Admin. Office-Ground floor, Shyam Nagar Colony, Maurya Path, Bailey Road, PO-B.V. College,Patna--800014
32	ENV Developmental Assistance Systems (India) Pvt. Ltd.	5224007470 9335913139	Details Of Qualification Attached	Rs. 2,750/- (Inclusive all Taxes)		Prabha Niketan, road No.-13,Patel Nagar, Near Petrol Pump, Patna-800029

Signature: *[Handwritten Signature]*

Stamp: PRANEJA ENVIROCARE & MANAGEMENT PVT. LTD. * RQP *

33	Indinine Pvt. Ltd.	9431040119	Bachelor of Engineering (Mining)	Rate for each District is enclosed	Enclosure A	H.No-21, First Floor, IAS Colony, S.K. Nagar, Patna-800001
34	M/S Sanyukt Infra	7296069668	Bachelor of Architecture	Rs. 3,500/-		South of Madhuban Housing complex, Malahi Pakdi, Kankarbagh-800020
35	Saathi Planners Pvt. Ltd.	9835877778	Details of qualification attached	Rs. 12,000/-		C/O Mr. Anil Kumar, plot No. L-171, Road No. 23 Near Malti Nikeran, Sri Krishna Nagar, Patna -800001
36	Overseas Min-Tech Consultants	9460221084	Details of qualification attached	Rs. 13,000/-		501, 5th Floor, Apex Tower, Tonk Road, Jaipur-302015, Tel-0141-2744509

3. प्राप्त सभी EOI की समीक्षा के उपरांत विभागीय समिति द्वारा सर्वसम्मति से खनन योजना हेतु देय राशि प्रति खनन योजना अधिकतम ₹30,000/- (तीस हजार) रू० GST सहित (चाहे माइनिंग प्लान कितने भी हेक्टेयर का हो) का भुगतान की अनुशंसा की गई।

4. समिति द्वारा उक्त न्यूनतम दर को स्वीकृत करते हुए उक्त न्यूनतम दर पर अभिरुचि की अभिव्यक्ति आमंत्रण में शामिल वैसे प्रतिष्ठान, जो वांछित योग्यता को पूरा करते हो तथा जिनका वर्तमान में पटना या बिहार राज्यान्तर्गत अन्य जिलों में कार्यालय संचालित है ऐसे प्रतिष्ठान को तत्काल प्रभाव से empanelled करने की अनुशंसा की जाती है।

शेष अन्य एजेंसी/व्यक्ति अगर भविष्य में बिहार राज्यान्तर्गत कार्यालय खोलने संबंधी साक्ष्य/दस्तावेज प्रस्तुत करते हैं तो उन्हें भी भविष्य में उक्त दर पर लघु खनिजों के खनन योजना तैयार करने हेतु RQP के रूप में empanelled करने की अनुशंसा की जाती है।

5. Empanelled एजेंसियों को अपने दस्तावेजों का सत्यापन विभागीय समिति से कराना आवश्यक होगा।

ह०/- स०आ०वि०स० सदस्य ह०/- स०नि० (मु०) सदस्य ह०/- अवर सचिव, सदस्य ह०/- उप निदेशक, पटना अंचल, पटना सदस्य ह०/- उप निदेशक (मु०), सदस्य ह०/- अपर सचिव-सह-निदेशक, अध्यक्ष

ह०/-
सरकार के अवर सचिव

ज्ञापांक:-...../एम०, दिनांक:-.....

प्रतिलिपि:- सभी समाहर्ता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ह०/-
सरकार के अवर सचिव

ज्ञापांक:-...../एम०, दिनांक:-.....

प्रतिलिपि:- सभी उप निदेशक/सभी सहायक निदेशक/सभी खनिज विकास पदाधिकारी/सभी खान निरीक्षक को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ह०/-
सरकार के अवर सचिव

प्रकाश कुमार



ज्ञापक:- 3825 / एम0, दिनांक- 07/11/19

प्रतिलिपि:- माननीय मंत्री के आप्त सचिव/प्रधान सचिव के प्रधान आप्त सचिव/निदेशक
कोषांग/उप निदेशक (मु0)/सहायक निदेशक (मु0)/खनिज विकास
पदाधिकारी (मु0) को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

प्रमाण
21/11/19

सरकार के अवर सचिव

श्रीकांत कुमार



ID PROOF OF THE APPLICANT

भारत सरकार
Government of India



श्रीकांत कुमार
Shreekanth Kumar
जन्म तिथि (DOB): 27/12/1992
लिंग: MALE

आधार कार्ड प्रमाण है, सत्यापन के साथ ही।
आधार कार्ड प्रमाण है, सत्यापन के साथ ही।
आधार कार्ड प्रमाण है, सत्यापन के साथ ही।
Aadhaar is proof of identity, date of citizenship
or date of birth. It should be used with verification (online
authentication, or scanning of QR code / offline BNA)

6995 1510 4521

मेरा आधार, मेरी पहचान

भारतीय विशिष्ट पहचान अधिकरण
Unique Identification Authority of India



श्री रामदास रॉय
S/C Ramdas Ray, Gachan, Bochana, PO
Bochana, Dist. Murshidabad
Bihar - 843103

6995 1510 4521
VID - 9196 5077 8968 1381

श्रीकांत कुमार

आयकर विभाग
INCOME TAX DEPARTMENT



भारत सरकार
GOVT. OF INDIA

स्थायी खाता संख्या कार्ड
Permanent Account Number Card

CHLPK1093F

नाम: श्रीकांत कुमार
SHREEKANT KUMAR

पिता का नाम: रामदास रॉय
RAMDAS RAY

जन्म तिथि: 27/12/1992



श्रीकांत कुमार



LAND DEED & REVENUE RECEIPT



Registration Department,
Government of Bihar



INDIA NON JUDICIAL



Other

First Party Name * : Not Applicable
Second Party Name * : SHREEKANT KUMAR AAYUSHMAN ENTERPRISES
Purchased By * : SHREEKANT KUMAR AAYUSHMAN ENTERPRISES
Certificate Number : BR038161211733898326132
Consideration Price : ₹0.00/-
Stamp Duty Paid : ₹1000.00/-
Registration Fee & Other Fees : ₹0.00/-
LLR & Proc Fee : ₹0.00/-
Miscellaneous Fees : ₹0.00/-
Discre SC : ₹0.00/-
Total Amount : ₹1000.00/- (One Thousand)



----- This stamp paper will only be valid if embossed below with special RED ink impression -----

Phone No:
Sold To/Issued To:

For Photo/ID Proof:
SHREEKANT KUMAR AAYUSHMAN ENTERPRISES



DEC-11-2021 12:03:06

₹ 0001000/-
ZERO ZERO ONE ZERO ZERO ZERO

20161211733310896981-00018363
3816121 2045

एकरारनामा

प्रथम पक्ष

1. श्री संजय कुमार, पिता- महेश चौधरी, श्री संजीत कुमार, पिता- हरेंद्र सिंह एवं श्रीमती आशा देवी, पति- अश्वनी कुमार
2. श्री पृथ्वी साहनी, पिता- माखन साहनी
3. श्री राजा साहनी, पिता- फौजदार साहनी, श्री राम बालक साहनी, श्री राम नाथ साहनी, श्री राम पुकार साहनी एवं राम जिनिश साहनी, पिता- राजा साहनी
4. श्री नथुनी साहनी, पिता- लालधारी साहनी, श्री राजेश कुमार, पिता- भुषण प्रसाद सिंह एवं बंदना कुमारी, पिता- दुर्गेश पराशार
5. श्री शिवनंदन ठाकुर, पिता- रास बिहारी ठाकुर एवं श्री देवी लाल साहनी, पिता- रूप लाल साहनी सभी ग्राम-पहेतिया, प्रखण्ड- हाजीपुर, जिला- वैशाली, बिहार, भारत के मुल निवासी हैं।

द्वितीय पक्ष

श्रीकान्त कुमार



श्री श्रीकांत कुमार, पिता- रामदास राय, ग्राम-गरहा, पो0- गरहा, प्रखण्ड- वोचहा, मुजफ्फरपुर, विहार-843103, भारत के मूल निवासी हैं एवं संरचना विकास परियोजना कार्य हेतु इन्हें मिट्टी की आवश्यकता है जिसके लिए इनके द्वारा प्रथम पक्ष से संपर्क स्थापित किया। प्रथम पक्ष का जमीन जो कि मौजा- पहेतिया, थाना सं0-60, अंचल-हाजीपुर, जिला- वैशाली, बिहार हैं।

जमीन का विवरण निम्न है-

क्र० सं०	रैयत का नाम	मौजा संख्या	खाता	खेसरा	रकबा (एकड़ में)
01	श्री संजय कुमार, श्री संजीत कुमार एवं श्रीमती आशा देवी	60	372	280	1.02
02	श्री पृथ्वी साहनी		139	281, 283	3.33
03	श्री राजा साहनी श्री राम बालक साहनी श्री राम नाथ साहनी श्री राम पुकार साहनी एवं राम जिनिश साहनी		139	282	1.78
04	श्री नथुनी साहनी श्री राजेश कुमार एवं बंदना कुमारी		63	284	1.05
05	श्री शिवनंदन ठाकुर एवं श्री देवी लाल साहनी		358	287	1.17
कुल					8.35

प्रथम पक्ष द्वितीय पक्ष उपरोक्त जमीन निम्नलिखित शर्तों पर देने को तैयार हुआ-

1. प्रथम पक्ष 2 वर्षों या कार्य समाप्ति (जो भी पहले हो) तक के लिए जमीन द्वितीय पक्ष को अधिकतम 2 मी० तक मिट्टी काटने को दे रहे हैं। जिसका भुगतान द्वितीय पक्ष द्वारा रू० 1,00,000/- प्रति एकड़ की दर से प्रथम पक्ष को ससमय करेंगे।
2. द्वितीय पक्ष उक्त जमीन से मिट्टी कटाई कर उसका इस्तेमाल संरचना विकास परियोजना कार्य में कर सकते हैं।
3. मिट्टी कटाई से संबंधित जरूरी सरकारी अनुमोदन की जिम्मेवारी द्वितीय पक्ष की होगी।
4. मिट्टी की रॉयल्टी, मालिकाना फिस एवं अन्य सरकारी शुल्क (मालगुजारी को छोड़ कर) के भुगतान की जिम्मेवारी द्वितीय पक्ष की होगी।
5. मिट्टी की खनन एवं धुलाई का खर्च द्वितीय पक्ष की जिम्मेवारी होगी।
6. प्रथम पक्ष मुख्य मार्ग से खनन क्षेत्र तक पहुँच पथ उपलब्ध कराएगी।

श्रीकांत कुमार



7. कार्य समाप्ति के बाद द्वितीय पक्ष उक्त जमीन को समतल बनाकर प्रथम पक्ष को सौंप देंगे।

दोनों पक्ष ने उपर्युक्त शर्तों को अच्छी तरह से पढ़कर समझ लिया है, उसके उपरांत गवाहों की उपस्थिति में अपना अपना हस्ताक्षर कर रहे हैं।

प्रथम पक्ष	द्वितीय पक्ष
1. श्री संजय कुमार - संजय कुमार	श्री श्रीकांत कुमार
2. श्री संजीत कुमार	
3. श्रीमती आशा देवी - Asha Devi	Aayushman Enterprises
4. श्री पृथ्वी साहनी	श्रीकांत कुमार
5. श्री राजा साहनी - देवानन्द साहनी	Proprietor
6. श्री राम बालक साहनी - अनिता साहनी	
7. श्री राम नाथ साहनी	
8. श्री राम पुकार साहनी - Raman Kumar	
9. राम जिनिश साहनी - Madan Kumar	
10. श्री नथुनी साहनी	
11. श्री राजेश कुमार - राजेश कुमार	
12. श्रीमती बंदना कुमारी - बंदना कुमारी	
13. श्री शिवनंदन ठाकुर	
14. श्री देवी लाल साहनी - देवी लाल साहनी	

गवाह—

श्रीकांत कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग
जमाबंदी पंजी प्रति

12/12/2024

भाग वर्तमान : 3पृष्ठ संख्या : 203जमाबन्दी संख्या : 826कंप्यूटरीकृत जमाबन्दी संख्या : 224127800072315

जिला का नाम : Vaishali
मौजा का नाम : पहेतिया

अनुमंडल नाम : Hajipur
होस्टिंग संख्या : N/A

अंचल का नाम : Hajipur
तोली संख्या : 0

हलका का नाम : पहेतिया
धाना नंबर : 60

देवी लाल साहनी , पिता/बाप/अबू - रूप लाल साहनी, जाति- N/A

खाता सं०	प्लॉट/खेसरा सं०	रकबा	चौहद्दी	परिवर्तन के लिए प्राधिकार	तगान	सेंस
358	267	0 ए 31 डि 0 हे	इ. प. उ. इ.	n/a	3.1	0
कुल परिमाण		0 ए 31 डि 0 हे				

अंतिम तगान का विवरण

तारीख	प्राप्ति पत्र सं०	साल से	साल तक	तागत बकाया
1900-01-01		2013	2014	0
2023-08-14 11:25:34	14082311244603511190	2014-2015	2023-2024	27.9

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है
किसी भी प्रकार की असुविधियों के लिए सम्बन्धित अंचलाधिकारी से संपर्क करें

श्रीमान कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

12/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 1	पृष्ठ संख्या : 626	जमाबंदी संख्या : 358	कंप्यूटरीकृत जमाबंदी संख्या : 224127800071848
जिला का नाम : Vaishali	अनुमंडल नाम : Hajipur	अंचल का नाम : Hajipur	हलका का नाम : पहेतिया
मौजा का नाम : पहेतिया	होलिंग संख्या : N/A	तैली संख्या : 0	घाना नंबर : 60

शिवनंदन ठाकुर, पिता/बाप/अवू-रास बिहारी ठाकुर, जाति-
N/A

खाता सं०	प्लॉट/खेसरा सं०	रकबा	बीहदी	परिवर्तन के लिए प्राधिकार	लगान	सेस
358	287	0 ए 86 डि 0 हे	एन उम	N/A	10	0
	कुल परिमाण	0 ए 86 डि 0 हे				

अंतिम लगान का विवरण

तारीख	प्राप्ति पत्र सं०	सात से	सात तक	लागत बकाया
1972-04-01	0	1972	1973	0

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Sl No	Case No	Mauja	Khata No	Plot No	Applicant Name	Application Date	Status
68240	3913 / 2024 - 2025	पहेतिया-60	358	287	ABAHY KUMAR RAUSHAN	05/08/2024	Status Pending at CO

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ड में दाखल मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है
किसी भी प्रकार की असुविधों के लिए सम्बन्धित अंशदाधिकारी से संपर्क करें

श्रीकांत कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

12/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 6	पृष्ठ संख्या : 54	जमाबंदी संख्या :	कंप्यूटरीकृत जमाबंदी संख्या : 224127800215549
जिला का नाम : Vaishali	अनुमंडल नाम : Hajipur	अंचल का नाम : Hajipur	हलका का नाम : पहेंतिया
मौजा का नाम : पहेंतिया	होस्टिंग संख्या : 63	तहसील संख्या :	धाना नंबर : 60

1. RAJESH KUMAR, पिता/बाप/अबू - BHUSHAN PRASAD SINGH, जति- N/A एवं 2. BANDANA KUMARI, पिता/बाप/अबू - DURGESH PARASHAR, जति- N/A

खाता सं०	प्लॉट/खेसरा सं०	रकबा	चौहद्दी	परिवर्तन के लिए प्राधिकार	लगान	सेस
63	264	0 ए 44 डि 0 है	ए- क-	नामान्तरण मुकदमा संख्या 1438/2021 - 2022	5	0
	कुल परिमाण	0 ए 44 डि 0 है				

अंतिम लगान का विवरण

तारीख	प्राप्ति पत्र सं०	साल से	साल तक	लागत बकाया
2021-12-02 10:01:14	02122021095938542869	2021-2022	2021-2022	0

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है
किसी भी प्रकार की अनुपुष्टियों के लिए सम्बंधित अंचलधिकारी से संपर्क करें

श्रीमान कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

12/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 1	पृष्ठ संख्या : 736	जमाबंदी संख्या : 468	कंप्यूटरीकृत जमाबंदी संख्या : 224127800071958
जिला का नाम : Vaishali	अनुमंडल नाम : Hajipur	अंचल का नाम : Hajipur	हलका का नाम : पहेंतिया
मौजा का नाम : पहेंतिया	होलिंग संख्या : N/A	तोजी संख्या : 0	धाना नंबर : 60

नयनी साहनी, पिता/दादा/अबू-सालाहरी साहनी, जाति- N/A					
खाला सं०	प्लाट/खेसरा सं०	रकबा	चौहद्दी	परिवर्तन के लिए प्राधिकार	लगान
63	284	0 ए 0 डि 0 हे	इ. पू. उ. पू.	n/a	61
	कुल परिमाण	0 ए 61 डि 0 हे			0

अंतिम लगान का विवरण		प्राप्ति पत्र सं०	सात से	सात तक	लागत बकाया
वारीख					
1900-01-01			1978	1979	0
2023-11-28 12:04:47	28112312003499318238		1979-1980	2023-2024	268.4
2024-07-31 08:35:39	31072408254245259327		2024-2025	2024-2025	0

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है
किसी भी प्रकार की अशुद्धियों के लिए सम्बंधित अधिकारी से संपर्क करें

श्रीमान कुमार





बिहार सरकार
राजस्व एवं भूमि सुधार विभाग

13/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 2	पृष्ठ संख्या : 61	जमाबंदी संख्या : 683	कंप्यूटरीकृत जमाबंदी संख्या : 224127800072173			
जिला का नाम : Vaishali	अनुमंडल नाम : Hajipur	अंचल का नाम : Hajipur	हलका का नाम : पहेंतिया			
मौजा का नाम : पहेंतिया	होलिंग संख्या : N/A	तहसील संख्या : 0	धाना नंबर : 60			
राम पुकार साहनी, पिता/बाप/अबू-राजा साहनी, जाति- N/A एवं राम खिनिश सहनी, पिता/बाप/अबू-राजा सहनी, जाति- N/A						
खता सं०	प्लॉट/खेसरा सं०	रकबा	घोहरी	परिवर्तन के लिए प्राधिकार	लगान	सेस
139	282	0 ए 0 डि 0 हे	ए० अ० ख०	N/A	9	0
कुल परिमाण		0 ए 89 डि 0 हे				
अंतिम लगान का विवरण						
तारीख	प्राप्ति पत्र सं०	साल से	साल तक	लागत बकाया		
1900-01-01		2016	2017	0		

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है

किसी भी प्रकार की अशुद्धियों के लिए सम्बन्धित अधिकारी से संपर्क करें

श्रीमानत कमल





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

13/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 2		पृष्ठ संख्या : 60		जमाबन्दी संख्या : 682		कंप्यूटरीकृत जमाबन्दी संख्या : 224127800072172							
जिला का नाम : Vaishali		अनुमंडल नाम : Hajipur		अंचल का नाम : Hajipur		हलका का नाम : पहेतिया							
मौजा का नाम : पहेतिया		होलिंग संख्या : N/A		तौजी संख्या : 0		धान नंबर : 60							
राजा साहनी, पिता/बाप/अबू : फौजदार साहनी, जाति: N/A एवं राम बालक साहनी, राम नाथ साहनी, पिता/बाप/अबू : राजा साहनी, जाति: N/A													
खारा सं०		प्लॉट/खेसरा सं०		रकबा		चौहद्दी		परिवर्तन के लिए प्राधिकार		लगान		सेरा	
139		282		0 ए 0 डि 0 हे		ए* अ* ध* ह*		n/a		9.1		0	
		कुल परिभाषित		0 ए 89 डि 0 हे									
अंतिम लगान का विवरण													
तारीख				प्राप्ति पत्र सं०				साल से		साल तक		लागत बकाया	
1900-01-01								2016		2017		0	
2022-06-13 11:06:33				13062022110540254560				2017-2018		2022-2023		45.5	

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दाखल मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

एक एक कम्प्यूटर जनित प्रति है
किसी भी प्रकार की अनधिकृतियों के लिए सम्बंधित अधिकारियों से संपर्क करें

श्रीमान कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

13/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 1		पृष्ठ संख्या : 405		जमाबन्दी संख्या : 139		कंप्यूटरीकृत जमाबन्दी संख्या : 224127800071628	
जिला का नाम : Vaishali		अनुमंडल नाम : Hajipur		अंचल का नाम : Hajipur		हलका का नाम : पहेतिया	
मौज का नाम : पहेतिया		होलिंग संख्या : N/A		तौजी संख्या : 0		फसल नंबर : 60	
पुष्पी साहनी, पिता/बाप/अबू, मकान साहनी, जाति: N/A							
खता सं०	खता/खसरा सं०	रकबा	चौहद्दी	परिवर्तन के लिए प्राधिकार	लगान	सेरा	
139	281	0 ए 0 डि 0 हे	ए- ए- उ- ड-	N/A	36.54	0	
	283	0 ए 0 डि 0 हे	ए- ए- उ- ड-				
	कुल परिमाण	3 ए 33 डि 0 हे					
अंतिम लगान का विवरण							
तारीख	प्राप्ति पत्र सं०	साल से	साल तक	साल तक	साल तक	साल तक	
1900-01-01		2009	2010		0		

उपरोक्त जमाबंदी के विरुद्ध दाखिल झारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है

किसी भी प्रकार की अपूर्णता के लिए सम्बंधित अधिकारी से संपर्क करें

श्रीकांत कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग
जमाबंदी पंजी प्रति

12/12/2024

भाग वर्तमान : 3

पृष्ठ संख्या : 270

जमाबंदी संख्या : 882

कंप्यूटरीकृत जमाबंदी संख्या : 224127800072382

जिला का नाम : Vaishali

मौजा का नाम : पहेतिया

अनुमंडल नाम : Hajipur

होलिंग संख्या : N/A

अंचल का नाम : Hajipur

तोड़ी संख्या : 0

हलका का नाम : पहेतिया

धाना नंबर : 60

अग्रा देवी, सोहर / पति-अश्वनी कुमार, जाति- N/A

खाता सं०	प्लॉट/खेसरा सं०	रकबा	बौहदी	परिवर्तन के लिए प्राधिकार	तगान	सेस
372	280	0 ए 0 डि 0 हे	बू- डू-	N/A	5	0
	कुल परिमाण	0 ए 24.75 डि 0 हे				

अंतिम तगान का विवरण

तारीख	प्राप्ति पत्र सं०	साल से	साल तक	लागत बकाया
1900-01-01		2016	2017	0
2024-06-09 17:10:40	09062404591066007793	2017-2018	2024-2025	35

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

इह एक कम्प्यूटर जनित प्रति है

किसी भी प्रकार की अशुद्धियों के लिए सम्बन्धित अधिकारी से संपर्क करें

श्रीमान कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

12/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 4	पृष्ठ संख्या : 908	जमाबंदी संख्या : 911	कंप्यूटरीकृत जमाबंदी संख्या : 224127800072401
जिला का नाम : Vaishali	अनुमंडल नाम : Hajipur	अंचल का नाम : Hajipur	हलका का नाम : पहेंतिया
मौजा का नाम : पहेंतिया	होस्टिंग संख्या : N/A	तौजी संख्या : 0	धाना नंबर : 60

संजीत कुमार, पिता/बाप/अबू - हरेंद्र सिंह, जाति- N/A

खाता सं०	प्लॉट/खेसरा सं०	रकबा	चौहद्दी	परिवर्तन के लिए प्राधिकार	लगान	सेस
372	280	0 ए 51 डि 0 हे	पू० उ०	n/a	10	0
	कुल परिमाण	0 ए 51 डि 0 हे				

अंतिम लगान का विवरण

तारीख	प्राप्ति पत्र सं०	सात से	सात तक	लागत बकाया
1900-01-01		2016	2017	0

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

यह एक कम्प्यूटर जनित प्रति है

किसी भी प्रकार की अशुद्धियों के लिए सम्बन्धित अंचलाधिकारी से संपर्क करें

समानत कुमार





बिहार सरकार
विहार सरकार
राजस्व एवं भूमि सुधार विभाग

12/12/2024

जमाबंदी पंजी प्रति

भाग वर्तमान : 5	पृष्ठ संख्या : 39	जमाबंदी संख्या :	कंप्यूटरीकृत जमाबंदी संख्या : 224127800188360			
जिला का नाम : Vaishali	अनुमंडल नाम : Hajipur	अंचल का नाम : Hajipur	हलका का नाम : पहेतिया			
मौज का नाम : पहेतिया	होलिंग संख्या : 372	लौकी संख्या :	धाना नंबर : 60			
श्री. संजय कुमार, पिता/बाप/अवु-श्री. नंदराम चौधरी, जाति-अवु						
खता सं०	प्लाट/खेसरा सं०	रकबा	चौहद्दी	परिवर्तन के लिए प्राधिकार	लगान	संस
372	280	0 ए 26 25 डि 0 हे	श्री. संजय कुमार	नमानाचण मुकदमा संख्या 5474/2018 - 2019	2.75	0
कुल परिमाण		0 ए 26 25 डि 0 हे				
अंतिम लगान का विवरण						
सारीख	प्राप्ति पत्र सं०	सात से	सात तक	तागव वकाया		

उपरोक्त जमाबंदी के विरुद्ध दाखिल खारिज का विवरण

Mutation Cases Not Found !!

उपरोक्त जमाबंदी के विरुद्ध भूमि बंधक (Land Mortgage) से सम्बंधित विवरण देखने के लिए यहाँ क्लिक करें

जमाबंदी में किये गए बदलाव का विवरण देखने के लिए यहाँ क्लिक करें

उपरोक्त जमाबंदी के विरुद्ध विभिन्न राजस्व कोर्ट में दायर मुकदमों का विवरण देखने के लिए यहाँ क्लिक करें

इस एक कम्प्यूटर जनित प्रति है
किसी भी प्रकार की अशुद्धियों के लिए स्थानिक अधिकारी से संपर्क करें

श्री. संजय कुमार




KHASRA MAP



Handwritten signature



COPY OF WORK ORDER/ SANCTION/LOI


 OnstruQ INTERLAYER PRIVATE LIMITED		EST. 2018			
WORK ORDER					
Billing Address OnstruQ Interlayer Pvt Ltd Deshpande, Lajpurni Vashi, Dist. 444101 Dist No. 10AADC02104M12Y Contact Person: Mr. Anil Dubey - 9862209265		Delivery Add: Village Chak Chamek, PO. Sarai Block Hajipur Near Fura Fyover Vastol Bihar 844125 Contact Person: Mr. Sandeep - 7983617894			
To: Aayushman Enterprises Garahan, Bocharan, Garahan Chowk, behind Central Bank, N.H. 57, Bocharan, Muzaffarpur Dist. PIN - 843103 GSTIN: 10CHLPK1093F22N		BANK DETAILS BENEFICIARY NAME - Shrookant Kumar ACCOUNT NO IFSC CODE BANK NAME Mob: +918210631805			
Sir, With reference to your quotation dated 01/12/24 and final negotiation on 09/12/2024 at site, we are pleased to inform you that your final offer to supply the soil has been accepted and supply order is awarded to you based on the terms & conditions mentioned in P.O. No. n/a. Payment will be made on any account.					
SNO	DESCRIPTION OF ITEMS	UNIT	QTY	BASIC RATE	REMARKS
1	Supply and filling Good earth excluding rock in trench or embankment in layers including compacting each layer by rolling, ramming and watering at complete as per drawings and direction of engineer-in-charge. (for filling, Compacted volume of soil to be measured and supply rate of compacted value to be provided) (note: Dewatering will be under the contractor's scope if required)	Mts	60000	295	
Terms & Conditions: 1. All work shall be done as per contract and will be made on any other account. 2. All work shall be done as per contract. 3. All necessary government documents or permit required will be in contractor's scope. 4. Material will be provided as per contract and will be in contractor's scope. 5. Any other liability for transportation or permit or other cost will be in contractor's scope. 6. Material will be provided as per contract and will be in contractor's scope. 7. Payment will be made on any account.		The work will be completed within 10 days from the date of award. All payments will be made within 10 days from the date of bill.			
 Authorized Signatory Office No. 10AADC02104M12Y, Deshpande, Lajpurni, Vashi, Dist. 444101		Aayushman Enterprises  Proprietor			
		FOR NO. 10AADC02104M12Y			



Handwritten signature/initials in blue ink.



PLATES & SITE PHOTOGRAPH



MINING SITE

Handwritten signature in blue ink.



Pahetiya Ordinary Earth Mining Project
At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar

SATELLITE-GOOGLE
500m BUFFER LOCATION MAP
OF THE STUDY AREA

Applicant: ☐ M/s Ayushman Enterprises
 Prop- Mr. Shrikant Kumar
 S/o Ramdas Ray
 At- Garha, P.S.- Bochaha, Muzaffarpur,
 Area: 3.38 Ha.,
 Mining Depth-2 m

Legend

GPS Point



Satellite.img

RGB



Red Layer 3

Green Layer 3

Blue Layer 3



Source
 SATELLITE-GOOGLE 2024




GPS Point

Gautam Kumar

Imagery Date: 5/29/2024

Imagery Date: 5/29/2024

Imagery Date: 5/29/2024



Pahetiya Ordinary Earth Mining Project

**At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar**

**Applicant: M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar**

**S/o Ramdas Ray
At- Garha, P.S.- Bochaha, Muzaffarpur,**

Area: 3.38 Ha..

Mining Depth-2 m

Index

● GPS Point

Contour (1m) interval

Mining Depth 2.0m

Geological Plan

Project Area

Agriculture Land (LU) Landuse

PLATE NO-1

SURFACE & GEOLOGICAL PLAN

**M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, P.S.- Bochaha, Muzaffarpur,**

**Pahetiya Ordinary Earth Mining Project
At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar**

Area: 3.38 Ha..



Mining Depth-2 m

SCALE: 1:1000

DATE OF SURVEY

PREPARED BY :-

SIGNATURE



Pahetiya Ordinary Earth Mining Project
At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar

Applicant: ☐ M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, P.S.- Bochaha, Muzaffarpur,
Area: 3.38 Ha..
Mining Depth-2 m

Index

-  GPS Point
-  Contour (1m) interval
-  Mining Depth 2.0m
-  Geological Plan
-  Project Area
-  Agriculture Land (LU) Landuse

PLATE NO-2

DEVELOPMENT PLAN

M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, P.S.- Bochaha, Muzaffarpur,

Pahetiya Ordinary Earth Mining Project
At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar
Area: 3.38 Ha..
Mining Depth-2 m
SCALE: 1:1000

DATE OF SURVEY

PREPARED BY :-

SIGNATURE



Handwritten signature/initials



Pahetiya Ordinary Earth Mining Project
At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar

Applicant: ☐ M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, P.S.- Bochaha, Muzaffarpur,
Area: 3.38 Ha..
Mining Depth-2 m

Index

- EMP 
- GPS Point 
- Contour (1m) Interval 
- Mining Depth 2.0m 
- Geological Plan 
- Project Area 
- Agriculture Land (LU) Landuse 

PLATE NO-3

EMP PLAN

M/s Aayushman Enterprises
Prop- Mr. Shrikant Kumar
S/o Ramdas Ray
At- Garha, P.S.- Bochaha, Muzaffarpur,

Pahetiya Ordinary Earth Mining Project
At Mauza- Pahetiya, Block-Hajipur
Distt.- Vaishali, Bihar
Area: 3.38 Ha..
Mining Depth-2 m
SCALE:- 1:1000

DATE OF SURVEY

PREPARED BY :-

SIGNATURE

M.B.P. 1/1/2019

